



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs


**Trial Pit No.  
TP21**



Style: TP PHOTOS File: P:\GINTWP\PROJECTS\26560.GPJ Printed: 07/03/2024 09:00:50 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator	FP
Chk & App	Status
FMR	FINAL

Title: **PHOTOGRAPHS OF TRIAL PITS**

Fig No:	 <b>C44</b>
---------	--



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP21**



Style: TP PHOTOS File: P:\GINTWPROJECTS\26560.GPJ Printed: 07/03/2024 09:00:50 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator FP	Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>
Chk & App FMR	Status FINAL	

	Fig No:  <b>C44</b>
--	---------------------------



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP22**



Style: TP PHOTOS File: P:\GINTWPROJECTS\26560.GPJ Printed: 07/03/2024 09:01:04 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator	FP
Chk & App	Status
FMR	FINAL

Title: **PHOTOGRAPHS OF TRIAL PITS**

Fig No: **C45**



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP22**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:01:04 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator FP	Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>
Chk & App FMR	Status FINAL	

	Fig No:  <b>C45</b>
--	---------------------------



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP23**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:01:19 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator	FP
Chk & App	Status
FMR	FINAL

Title: **PHOTOGRAPHS OF TRIAL PITS**

Fig No: **C46**



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560


Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP23**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:01:19 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator FP	Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>	 Fig No:  <b>C46</b>
Chk & App FMR	Status FINAL		



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs


**Trial Pit No.  
TP24**



Style: TP PHOTOS File: P:\GINTWPROJECTS\26560.GPJ Printed: 07/03/2024 09:01:33 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator	FP
Chk & App	Status
FMR	FINAL

Title: **PHOTOGRAPHS OF TRIAL PITS**

Fig No:	 <b>C47</b>
---------	--



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP24**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:01:33 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator FP
Chk & App FMR	Status FINAL

Title:  
**PHOTOGRAPHS OF TRIAL PITS**

Fig No:  
**C47**





Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP25**



Style: TP PHOTOS File: P:\GINTWPROJECTS\26560.GPJ Printed: 07/03/2024 09:01:45 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator	Title:
	FP	PHOTOGRAPHS OF TRIAL PITS
Chk & App	Status	
FMR	FINAL	

	Fig No:
	C48



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission


Engineer: Jacobs

**Trial Pit No.  
TP25**



Style: TP PHOTOS File: P:\GINTWPROJECTS\26560.GPJ Printed: 07/03/2024 09:01:45 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator FP	Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>
Chk & App FMR	Status FINAL	

	Fig No:   <b>C48</b>
--	--



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP26**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:01:59 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator	FP
Chk & App	Status
FMR	FINAL

Title: **PHOTOGRAPHS OF TRIAL PITS**

Fig No: **C49**



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP26**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:01:59 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator  
FP

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:



C49

Chk & App  
FMR

Status  
FINAL



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP27**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:02:09 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator	FP
Chk & App	Status
FMR	FINAL

Title: **PHOTOGRAPHS OF TRIAL PITS**

Fig No:	<b>C50</b>
---------	------------



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP28**



Style: TP PHOTOS File: P:\GINTWPROJECTS\26560.GPJ Printed: 07/03/2024 09:02:23 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator	FP
Chk & App	Status
FMR	FINAL

Title: **PHOTOGRAPHS OF TRIAL PITS**

Fig No: **C51**



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560


Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP28**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:02:23 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator FP	Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>	Fig No:   <b>C51</b>
Chk & App FMR	Status FINAL		



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP29**



Style: TP PHOTOS File: P:\GINTWPROJECTS\26560.GPJ Printed: 07/03/2024 09:02:37 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator FP	Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>
Chk & App FMR	Status FINAL	

	Fig No:  <b>C52</b>
--	---------------------------





Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP29**



Style: TP PHOTOS File: P:\GINTWPROJECTS\26560.GPJ Printed: 07/03/2024 09:02:37 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator	Title:
	FP	PHOTOGRAPHS OF TRIAL PITS
Chk & App	Status	
FMR	FINAL	

	Fig No:
	C52



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP30**



Style: TP PHOTOS File: P:\GINTWPROJECTS\26560.GPJ Printed: 07/03/2024 09:02:47 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator	FP
Chk & App	Status
FMR	FINAL

Title: **PHOTOGRAPHS OF TRIAL PITS**

Fig No: **C53**



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP31**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:03:30 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator	FP
Chk & App	Status
FMR	FINAL

Title: **PHOTOGRAPHS OF TRIAL PITS**

Fig No: **C54**



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560


Client: SSEN Transmission


Engineer: Jacobs


**Trial Pit No.  
TP31**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:03:30 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator FP	Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>	 Fig No:  <b>C54</b>
Chk & App FMR	Status FINAL		

		Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>	 Fig No:  <b>C54</b>
Chk & App FMR	Status FINAL		

		Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>	 Fig No:  <b>C54</b>
Chk & App FMR	Status FINAL		



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560


Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP32**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:03:45 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator FP	Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>	Fig No:   <b>C55</b>
Chk & App FMR	Status FINAL		



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560


Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP32**



Style: TP PHOTOS File: P:\GINTWPROJECTS\26560.GPJ Printed: 07/03/2024 09:03:45 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator FP	Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>		Fig No:  <b>C55</b>
Chk & App FMR	Status FINAL			



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs


**Trial Pit No.  
TP33**



Style: TP PHOTOS File: P:\GINTWPROJECTS\26560.GPJ Printed: 07/03/2024 09:03:57 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator	FP
Chk & App	Status
FMR	FINAL

Title: **PHOTOGRAPHS OF TRIAL PITS**

Fig No:	 <b>C56</b>
---------	--



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560


Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP33**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:03:57 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator FP	Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>		Fig No:  <b>C56</b>
Chk & App FMR	Status FINAL			





Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP34**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:04:10 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator	FP
Chk & App	Status
FMR	FINAL

Title: **PHOTOGRAPHS OF TRIAL PITS**

Fig No: **C57**



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560


Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP34**



Style: TP PHOTOS File: P:\GINTWPROJECTS\26560.GPJ Printed: 07/03/2024 09:04:10 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator FP	Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>		Fig No:  <b>C57</b>
Chk & App FMR	Status FINAL			



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP35**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:04:24 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator	FP
Chk & App	Status
FMR	FINAL

Title: **PHOTOGRAPHS OF TRIAL PITS**

Fig No: **C58**



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560


Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP35**



Style: TP PHOTOS File: P:\GINTWPROJECTS\26560.GPJ Printed: 07/03/2024 09:04:24 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator FP	Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>		Fig No:  <b>C58</b>
Chk & App FMR	Status FINAL			



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP36**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:04:38 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator	FP
Chk & App	Status
FMR	FINAL

Title: **PHOTOGRAPHS OF TRIAL PITS**

Fig No: **C59**



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560


Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP36**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:04:38 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator FP	Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>		Fig No:  <b>C59</b>
Chk & App FMR	Status FINAL			




Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP36A**



Date: 13/12/23  
Project: Fasnakyle  
Project No: 26560  
TP: TP36A  
Depth: 0.80m



Date: 13/12/23  
Project: Fasnakyle  
Project No: 26560  
TP: TP36A  
Depth: 0.80m

Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:04:49 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator	FP
Chk & App	Status
FMR	FINAL

Title: **PHOTOGRAPHS OF TRIAL PITS**

Fig No: **C60**



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP36A**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:04:49 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator	Title:
	FP	PHOTOGRAPHS OF TRIAL PITS
Chk & App	Status	
FMR	FINAL	

	Fig No:
	C60





Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP37**



Style: TP PHOTOS File: P:\GINTWPROJECTS\26560.GPJ Printed: 07/03/2024 09:05:02 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator	Title:
	FP	<b>PHOTOGRAPHS OF TRIAL PITS</b>
Chk & App	Status	
FMR	FINAL	

	Fig No:
	<b>C61</b>



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**Trial Pit No.  
TP37**



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26560.GPJ Printed: 07/03/2024 09:05:02 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator FP	Title:  <b>PHOTOGRAPHS OF TRIAL PITS</b>
Chk & App FMR	Status FINAL	

	Fig No:  <b>C61</b>
--	---------------------------



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

Style: APPENDIX D File: P:\GINTWPROJECTS\26560.GPJ Printed: 23/01/2024 09:19:03 Raeburn Drilling and Geotechnical Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

APPENDIX D  
IN-SITU TESTING






TP ID	Test Depth (m)	Date & Time of Test	Read Time	Ambient Soil Temperature (°C)	Strata Type	Ground-water Level (m)	NMC (%)	Thermal Conductivity (W/K m)	Thermal Resistivity (K m/W)	Remarks
TP01	1.1	29.11/23	150	6.9	SAND & GRAVEL	1.1		1.079	0.9267841	
TP08	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Unsuitable material
TP10	1.1	24.11.23	150	6.9	Gravelly SAND	1.75m	N/A	1.826	0.5476451	
TP12	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Unsuitable material
TP13	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Unsuitable material
TP14	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Unsuitable material
TP15	1.1	27.11.23	150	7.3	PEAT	1.75m		1.325	0.754717	
TP19	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Unsuitable material
TP20	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Unsuitable material
TP26	1.1	24.11.23	150	7.03	PEAT	0.30m		1.251	0.7993605	
TP27	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Unsuitable material
TP28	1.1	21.11.23	150	7.1	SAND & GRAVEL	2.90m	6.4	5.232	0.1911315	
TP30	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Unsuitable material
TP34	1	21.11.23	150	7.05	SAND & GRAVEL	1.80m		0.717	1.3947001	
TP37	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Unsuitable material



INDETERMINATE

	IM

**SOAKAWAY**



Fig No:

D2



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

APPENDIX E  
MONITORING





Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission  
 Engineer: Jacobs

\* Water level measurements taken from ground level.

Style: SPIPE MONITORING File: P:\GINTW\PROJECTS\26560.GPJ Printed: 23/05/2024 11:56:08 Raeburn Drilling and Geotechnical Whistleberry Rd, Hamilton ML3 QHP Tel: 01898-711177 E-mail: enquiries@raeburndrilling.com

Borehole No.	Surveyed Level (m OD)	Depth to Base of Standpipe (m)	Date	Atmospheric Pressure (mBar)	Gas Composition					Differential Pressure (Pa)	Flow (l/hr)	Depth to Water (m) (mBGL)	Depth (mOD)	Remarks
					CH <sub>4</sub> (%vol)	CO <sub>2</sub> (%vol)	O <sub>2</sub> (%vol)	H <sub>2</sub> S (ppm)	CO (ppm)					
BH02	324.21		30/01/24 09:00	984	0.00	0.10	19.60	0.00	0.00	0.00	0.00	1.26	322.95	Dry, Overcast
	324.21		30/01/24 09:01		0.00	0.10	19.50	0.00	0.00					Dry, Overcast
	324.21		30/01/24 09:02		0.00	0.10	19.50	0.00	0.00					Dry, Overcast
	324.21		30/01/24 09:03		0.00	0.10	19.50	0.00	2.00					Dry, Overcast
	324.21		30/01/24 09:04		0.00	0.10	19.50	1.00	3.00					Dry, Overcast
	324.21		30/01/24 09:05		0.00	0.10	19.50	0.00	2.00					Dry, Overcast
	324.21		29/02/24 09:00	952	0.00	0.00	19.30	0.00	0.00	18.00	3.10	0.42	323.79	Overcast, raining
	324.21		29/02/24 09:01		0.00	0.00	19.00	0.00	1.00					Overcast, raining
	324.21		29/02/24 09:02		0.00	0.00	19.30	0.00	2.00					Overcast, raining
	324.21		29/02/24 09:03		0.00	0.00	19.20	0.00	1.00					Overcast, raining
	324.21		29/02/24 09:04		0.00	0.00	19.20	0.00	1.00					Overcast, raining
	324.21		29/02/24 09:05		0.00	0.00	19.10	0.00	0.00		2.90			Overcast, raining
	324.21		25/03/24 12:54	961	0.00	0.00	17.20	0.00	0.00	0.00	0.00	5.06	319.15	Overcast, occasional snow
	324.21		25/03/24 12:55		0.00	0.00	17.20	0.00	0.00					Overcast, occasional snow
	324.21		25/03/24 12:56		0.00	0.00	16.50	0.00	0.00					Overcast, occasional snow
	324.21		25/03/24 12:57		0.00	0.00	15.80	0.00	0.00					Overcast, occasional snow
	324.21		25/03/24 12:58		0.00	0.00	15.40	0.00	0.00					Overcast, occasional snow
	324.21		25/03/24 12:59		0.00	0.00	15.20	0.00	0.00					Overcast, occasional snow
	324.21		23/04/24 11:24	989	0.00	2.10	17.20	0.00	10.00	0.00	0.00	4.73	319.48	Dry, overcast and cool
	324.21		23/04/24 11:25		0.00	2.20	16.70	0.00	5.00					Dry, overcast and cool
	324.21		23/04/24 11:26		0.00	2.20	16.70	0.00	3.00					Dry, overcast and cool
	324.21		23/04/24 11:27		0.00	2.20	16.70	0.00	0.00					Dry, overcast and cool
	324.21		23/04/24 11:28		0.00	2.20	16.80	0.00	2.00					Dry, overcast and cool
	324.21		23/04/24 11:29		0.00	2.20	16.80	0.00	1.00					Dry, overcast and cool
BH04	325.02		01/02/24 09:00	987	0.00	0.00	19.20	0.00	0.00	0.00	0.40	0.43	324.59	Dry, Overcast
	325.02		01/02/24 09:01		0.00	0.00	19.30	0.00	0.00					Dry, Overcast
	325.02		01/02/24 09:02		0.00	0.00	19.20	0.00	0.00					Dry, Overcast
	325.02		01/02/24 09:03		0.00	0.00	19.20	0.00	0.00					Dry, Overcast
	325.02		01/02/24 09:04		0.00	0.00	19.20	0.00	0.00					Dry, Overcast
	325.02		01/02/24 09:05		0.00	0.00	19.20	0.00	0.00					Dry, Overcast
	325.02		29/02/24 09:00	952	0.00	0.00	19.30	0.00	0.00	0.00	0.00	0.42	324.60	Overcast, raining
	325.02		29/02/24 09:01		0.00	0.00	19.20	0.00	1.00					Overcast, raining
	325.02		29/02/24 09:02		0.00	0.00	19.30	0.00	0.00					Overcast, raining
	325.02		29/02/24 09:03		0.00	0.00	19.30	0.00	1.00					Overcast, raining
	325.02		29/02/24 09:04		0.00	0.00	19.20	0.00	0.00					Overcast, raining
	325.02		29/02/24 09:05		0.00	0.00	19.20	0.00	0.00		0.00			Overcast, raining
	325.02		25/03/24 13:49	961	0.00	0.00	18.10	0.00	0.00	-3.00	-0.40	0.54	324.48	Overcast, occasional snow
	325.02		25/03/24 13:50		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	325.02		25/03/24 13:51		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	325.02		25/03/24 13:52		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	325.02		25/03/24 13:53		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	325.02		25/03/24 13:54		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	325.02		23/04/24 12:14	988	0.00	1.40	19.00	0.00	0.00	0.00	0.00	0.58	324.44	Dry, overcast and cool
	325.02		23/04/24 12:15		0.00	2.00	17.10	0.00	0.00					Dry, overcast and cool

Originator	Title:			Fig No:
JMcM Status FMR	<b>RESULTS OF GAS AND WATER LEVEL MONITORING IN STANDPIPES</b>			<b>E2</b> Sheet 1 of 7



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission  
 Engineer: Jacobs

\* Water level measurements taken from ground level.

Borehole No.	Surveyed Level (m OD)	Depth to Base of Standpipe (m)	Date	Atmospheric Pressure (mBar)	Gas Composition					Differential Pressure (Pa)	Flow (l/hr)	Depth to Water (m) (mBGL)	Depth (mOD)	Remarks
					CH <sub>4</sub> (%vol)	CO <sub>2</sub> (%vol)	O <sub>2</sub> (%vol)	H <sub>2</sub> S (ppm)	CO (ppm)					
BH04	325.02		23/04/24 12:16		0.00	2.00	17.30	0.00	0.00					Dry, overcast and cool
	325.02		23/04/24 12:17		0.00	2.00	17.30	0.00	0.00					Dry, overcast and cool
	325.02		23/04/24 12:18		0.00	1.90	17.40	0.00	0.00					Dry, overcast and cool
	325.02		23/04/24 12:19		0.00	1.90	17.50	0.00	0.00					Dry, overcast and cool
BH08	334.07		12/01/23 00:00									0.00	334.07	
	334.07		15/12/23 00:00									0.00	334.07	
	334.07		19/12/23 00:00									0.00	334.07	
	334.07		30/01/24 00:00									0.30	333.77	Water level 0.30m above GL
	334.07		29/02/24 09:00									0.30	333.77	Water level 0.30m above GL
	334.07		25/03/24 12:40									0.20	333.87	Water level 0.20m above GL
	334.07		23/04/24 11:09									0.30	333.77	Water level 0.30m above GL
BH11	330.59		19/12/23 00:00									4.02	326.57	
	330.59		11/01/24 00:00									4.51	326.08	
	330.59		30/01/24 09:00	984	0.00	0.00	18.90	0.00	0.00	0.00	0.30	3.55	327.04	Dry, Overcast
	330.59		30/01/24 09:01		0.00	0.00	19.00	0.00	0.00					Dry, Overcast
	330.59		30/01/24 09:02		0.00	0.00	19.00	0.00	1.00					Dry, Overcast
	330.59		30/01/24 09:03		0.00	0.00	19.00	0.00	0.00					Dry, Overcast
	330.59		30/01/24 09:04		0.00	0.00	18.90	0.00	0.00					Dry, Overcast
	330.59		29/02/24 09:00	950	0.00	0.00	18.00	0.00	0.00	6.00	2.00	4.85	325.74	Overcast, raining
	330.59		29/02/24 09:01		0.00	0.00	19.20	1.00	0.00					Overcast, raining
	330.59		29/02/24 09:02		0.00	0.10	19.10	1.00	1.00					Overcast, raining
	330.59		29/02/24 09:03		0.00	0.00	19.20	1.00	0.00					Overcast, raining
	330.59		29/02/24 09:04		0.00	0.00	19.20	0.00	1.00					Overcast, raining
	330.59		29/02/24 09:05		0.00	0.00	19.10	0.00	0.00		1.30			Overcast, raining
	330.59		25/03/24 13:18	960	0.00	0.00	17.70	0.00	0.00	-2.00	-0.40	4.81	325.78	Overcast, occasional snow
	330.59		25/03/24 13:19		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	330.59		25/03/24 13:20		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	330.59		25/03/24 13:21		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	330.59		25/03/24 13:22		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	330.59		25/03/24 13:23		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	330.59		23/04/24 11:46	988	0.00	1.60	18.20	0.00	0.00	0.00	0.00	4.44	326.15	Dry, overcast and cool
	330.59		23/04/24 11:47		0.00	2.20	16.40	0.00	0.00					Dry, overcast and cool
	330.59		23/04/24 11:48		0.00	2.10	16.40	0.00	0.00					Dry, overcast and cool
	330.59		23/04/24 11:49		0.00	2.10	16.60	0.00	0.00					Dry, overcast and cool
	330.59		23/04/24 11:50		0.00	2.10	16.70	0.00	0.00					Dry, overcast and cool
	330.59		23/04/24 11:51		0.00	2.10	16.80	0.00	0.00					Dry, overcast and cool
BH14	306.06		15/12/23 00:00									0.15	305.91	
	306.06		19/12/23 00:00									0.11	305.95	
	306.06		11/01/24 00:00									0.36	305.70	
	306.06		31/01/24 09:00	962	0.00	0.00	19.30	0.00	0.00	0.00	0.00	0.27	305.79	Overcast, raining
	306.06		31/01/24 09:01		0.00	0.10	19.40	0.00	0.00					Overcast, raining
	306.06		31/01/24 09:02		0.00	0.10	19.30	0.00	0.00					Overcast, raining
	306.06		31/01/24 09:03		0.00	0.10	19.30	0.00	0.00					Overcast, raining
	306.06		31/01/24 09:04		0.00	0.10	19.30	0.00	1.00					Overcast, raining

Style: SPIPE MONITORING File: P:\GINTW\PROJECTS\26560.GPJ Printed: 23/05/2024 11:56:09 Raeburn Drilling and Geotechnical Whistleberry Rd, Hamilton ML3 OHP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator	Title: RESULTS OF GAS AND WATER LEVEL MONITORING IN STANDPIPES										Fig No:
JMCM											E2
Chk & App	Status										
FMR	Final										





Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission  
 Engineer: Jacobs

\* Water level measurements taken from ground level.

Borehole No.	Surveyed Level (m OD)	Depth to Base of Standpipe (m)	Date	Atmospheric Pressure (mBar)	Gas Composition					Differential Pressure (Pa)	Flow (l/hr)	Depth to Water (m) (mBGL)	Depth (mOD)	Remarks
					CH <sub>4</sub> (%vol)	CO <sub>2</sub> (%vol)	O <sub>2</sub> (%vol)	H <sub>2</sub> S (ppm)	CO (ppm)					
BH14	306.06		31/01/24 09:05		0.00	0.10	19.30	0.00	0.00					Overcast, raining
	306.06		28/02/24 09:00	961	0.00	0.00	19.30	0.00	1.00	0.00	0.00	0.22	305.84	Overcast, raining
	306.06		28/02/24 09:01		0.00	0.10	19.50	0.00	0.00					Overcast, raining
	306.06		28/02/24 09:02		0.00	0.10	19.50	0.00	0.00					Overcast, raining
	306.06		28/02/24 09:03		0.00	0.10	19.50	0.00	1.00					Overcast, raining
	306.06		28/02/24 09:04		0.00	0.10	19.40	0.00	0.00					Overcast, raining
	306.06		28/02/24 09:05		0.00	0.10	19.40	0.00	0.00		0.00			Overcast, raining
	306.06		26/03/24 08:42	960	0.00	0.00	17.60	0.00	0.00	-2.00	-0.30	0.24	305.82	Overcast, occasional snow
	306.06		26/03/24 08:43		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	306.06		26/03/24 08:44		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	306.06		26/03/24 08:45		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	306.06		26/03/24 08:46		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	306.06		26/03/24 08:47		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	306.06		22/04/24 16:48	997	0.00	0.40	15.00	0.00	0.00	0.00	0.00	0.27	305.79	Dry, sunny and mild
	306.06		22/04/24 16:49		0.00	1.00	19.50	0.00	0.00					Dry, sunny and mild
	306.06		22/04/24 16:50			1.10								Test terminated due to water ingress
BH16	325.42		19/12/23 00:00									0.54	324.88	
	325.42		12/01/24 00:00									0.62	324.80	
	325.42		01/02/24 09:00	987	0.00	0.00	18.90	0.00	1.00	2.00	0.80	0.62	324.80	Dry, Overcast
	325.42		01/02/24 09:01		0.00	0.00	19.20	0.00	1.00					Dry, Overcast
	325.42		01/02/24 09:02		0.00	0.00	19.10	0.00	0.00					Dry, Overcast
	325.42		01/02/24 09:03		0.00	0.00	19.10	0.00	0.00					Dry, Overcast
	325.42		01/02/24 09:04		0.00	0.00	19.10	0.00	0.00					Dry, Overcast
	325.42		01/02/24 09:05		0.00	0.00	19.10	0.00	0.00					Dry, Overcast
	325.42		28/02/24 09:00	962	0.00	0.10	19.60	0.00	0.00	0.00	0.00	0.70	324.72	Overcast, raining
	325.42		28/02/24 09:01		0.00	0.10	19.50	0.00	1.00					Overcast, raining
	325.42		28/02/24 09:02		0.00	0.10	19.50	0.00	2.00					Overcast, raining
	325.42		28/02/24 09:03		0.00	0.10	19.50	0.00	1.00					Overcast, raining
	325.42		28/02/24 09:04		0.00	0.10	19.50	1.00	1.00					Overcast, raining
	325.42		28/02/24 09:05		0.00	0.10	19.40	0.00	1.00		0.00			Overcast, raining
	325.42		25/03/24 13:37	960	0.00	0.00	17.80	0.00	0.00	-4.00	-0.40	0.70	324.72	Overcast, occasional snow
	325.42		25/03/24 13:38		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	325.42		25/03/24 13:39		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	325.42		25/03/24 13:40		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	325.42		25/03/24 13:41		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	325.42		25/03/24 13:42		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	325.42		23/04/24 12:03	989	0.00	1.60	20.10	0.00	0.00	0.00	0.00	1.10	324.32	Dry, overcast and cool
	325.42		23/04/24 12:04		0.00	2.10	17.40	0.00	0.00					Dry, overcast and cool
	325.42		23/04/24 12:05		0.00	2.00	17.50	0.00	0.00					Dry, overcast and cool
	325.42		23/04/24 12:06		0.00	2.00	17.60	0.00	0.00					Dry, overcast and cool
	325.42		23/04/24 12:07		0.00	2.00	17.60	0.00	1.00					Dry, overcast and cool
	325.42		23/04/24 12:08		0.00	2.00	17.70	0.00	0.00					Dry, overcast and cool
BH18	316.75		08/12/23 00:00									1.95	314.80	

Style: SPIPE MONITORING File: P:\GINTW\PROJECTS\26560.GPJ Printed: 23/05/2024 11:56:09 Reaburn Drilling and Geotechnical Whistleberry Rd, Hamilton ML3 OHP Tel: 01898-711177 E-mail: enquiries@reaburndrilling.com

Originator <b>JMcM</b>		Title: <b>RESULTS OF GAS AND WATER LEVEL MONITORING IN STANDPIPES</b>										Fig No: <b>E2</b>	
Chk & App <b>FMR</b>	Status <b>Final</b>											Sheet 3 of 7	



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission  
 Engineer: Jacobs

\* Water level measurements taken from ground level.

Style: SPIPE MONITORING File: P:\GINTW\PROJECTS\26560.GPJ Printed: 23/05/2024 11:56:09 Raeburn Drilling and Geotechnical Whistleberry Rd, Hamilton ML3 QHP Tel: 01898-711177 E-mail: enquiries@raeburndrilling.com

Borehole No.	Surveyed Level (m OD)	Depth to Base of Standpipe (m)	Date	Atmospheric Pressure (mBar)	Gas Composition					Differential Pressure (Pa)	Flow (l/hr)	Depth to Water (m) (mBGL)	Depth (mOD)	Remarks
					CH <sub>4</sub> (%vol)	CO <sub>2</sub> (%vol)	O <sub>2</sub> (%vol)	H <sub>2</sub> S (ppm)	CO (ppm)					
BH18	316.75		15/12/23 00:00									1.98	314.77	
	316.75		19/12/23 00:00									1.96	314.79	
	316.75		11/01/24 00:00									2.00	314.75	
	316.75		31/01/24 09:00	962	0.00	0.10	19.40	0.00	1.00	0.00	0.00	0.50	316.25	Overcast, raining
	316.75		31/01/24 09:01		0.00	0.10	19.30	0.00	0.00					Overcast, raining
	316.75		31/01/24 09:02		0.00	0.10	19.30	0.00	0.00					Overcast, raining
	316.75		31/01/24 09:03		0.00	0.10	19.30	0.00	1.00					Overcast, raining
	316.75		31/01/24 09:04		0.00	0.10	19.30	0.00	1.00					Overcast, raining
	316.75		31/01/24 09:05		0.00	0.10	19.30	0.00	1.00					Overcast, raining
	316.75		28/02/24 09:00	966	0.00	0.10	18.20	0.00	0.00	5.00	1.30	1.84	314.91	Overcast, raining
	316.75		28/02/24 09:01		0.00	0.10	19.40	0.00	0.00					Overcast, raining
	316.75		28/02/24 09:02		0.00	0.10	19.40	0.00	0.00					Overcast, raining
	316.75		28/02/24 09:03		0.00	0.10	19.40	0.00	0.00					Overcast, raining
	316.75		28/02/24 09:04		0.00	0.10	19.30	0.00	0.00					Overcast, raining
	316.75		28/02/24 09:05		0.00	0.10	19.30	0.00	0.00		1.30			Overcast, raining
	316.75		26/03/24 08:59	958	0.00	0.00	17.80	0.00	0.00	-3.00	-0.40	1.87	314.88	Overcast, occasional snow
	316.75		26/03/24 09:00		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	316.75		26/03/24 09:01		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	316.75		26/03/24 09:02		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	316.75		26/03/24 09:03		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	316.75		26/03/24 09:04		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	316.75		22/04/24 09:00	992	0.00	0.60	19.60	0.00	0.00	-8.00	-2.10	1.59	315.16	Dry, sunny and mild
	316.75		22/04/24 09:01		0.00	0.00	8.80	0.00	0.00					Dry, sunny and mild
	316.75		22/04/24 09:02		0.00	0.00	7.00	0.00	0.00					Dry, sunny and mild
	316.75		22/04/24 09:03		0.00	0.00	0.40	0.00	0.00					Dry, sunny and mild
	316.75		22/04/24 09:04		0.00	0.00	6.00	0.00	0.00					Dry, sunny and mild
	316.75		22/04/24 09:05		0.00	0.00	6.20	0.00	0.00		-1.40			Dry, sunny and mild
BH21	326.49		01/12/23 00:00									0.25	326.24	
	326.49		08/12/23 00:00									0.33	326.16	
	326.49		15/12/23 00:00									0.36	326.13	
	326.49		19/12/23 00:00									0.30	326.19	
	326.49		12/01/24 00:00									0.35	326.14	
	326.49		31/01/24 09:00	961	0.00	0.10	19.10	0.00	1.00	0.00	0.00	0.28	326.21	Overcast, raining
	326.49		31/01/24 09:01		0.00	0.10	19.20	0.00	0.00					Overcast, raining
	326.49		31/01/24 09:02		0.00	0.10	19.20	0.00	1.00					Overcast, raining
	326.49		31/01/24 09:03		0.00	0.10	19.20	0.00	1.00					Overcast, raining
	326.49		31/01/24 09:04		0.00	0.10	19.20	0.00	0.00					Overcast, raining
	326.49		31/01/24 09:05		0.00	0.10	19.10	0.00	1.00					Overcast, raining
	326.49		28/02/24 09:00	962	0.00	0.10	19.10	0.00	0.00	0.00	0.00	0.27	326.22	Overcast, raining
	326.49		28/02/24 09:01		0.00	0.10	19.30	0.00	1.00					Overcast, raining
	326.49		28/02/24 09:02		0.00	0.10	19.40	0.00	1.00					Overcast, raining
	326.49		28/02/24 09:03		0.00	0.10	19.40	0.00	0.00					Overcast, raining
	326.49		28/02/24 09:04		0.00	0.10	19.40	0.00	0.00					Overcast, raining
	326.49		28/02/24 09:05		0.00	0.10	19.40	0.00	0.00		0.00			Overcast, raining

Chk & App <b>FMR</b>	Originator <b>JMcM</b>	Title: <b>RESULTS OF GAS AND WATER LEVEL MONITORING IN STANDPIPES</b>		Fig No: <b>E2</b>
	Status <b>Final</b>			Sheet 4 of 7



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission  
 Engineer: Jacobs

\* Water level measurements taken from ground level.

Style: SPIPE MONITORING File: P:\GINTW\PROJECTS\26560.GPJ Printed: 23/05/2024 11:56:09 Raeburn Drilling and Geotechnical Whistleberry Rd, Hamilton ML3 QHP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Borehole No.	Surveyed Level (m OD)	Depth to Base of Standpipe (m)	Date	Atmospheric Pressure (mBar)	Gas Composition					Differential Pressure (Pa)	Flow (l/hr)	Depth to Water (m) (mBGL)	Depth (mOD)	Remarks
					CH <sub>4</sub> (%vol)	CO <sub>2</sub> (%vol)	O <sub>2</sub> (%vol)	H <sub>2</sub> S (ppm)	CO (ppm)					
BH21	326.49		26/03/24 09:19	956	0.00	0.00	17.80	0.00	0.00	-0.30	-0.50	0.31	326.18	Overcast, occasional snow
	326.49		26/03/24 09:20		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	326.49		26/03/24 09:21		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	326.49		26/03/24 09:22		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	326.49		26/03/24 09:23		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	326.49		26/03/24 09:24		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	326.49		22/04/24 15:47	992	0.00	0.20	19.20	0.00	0.00	0.00	0.00	0.34	326.15	Dry, sunny and mild
	326.49		22/04/24 15:48		0.00	1.00	17.50	0.00	0.00					Dry, sunny and mild
	326.49		22/04/24 15:49		0.00	1.10	17.50	0.00	0.00					Dry, sunny and mild
	326.49		22/04/24 15:50		0.00	1.20	17.40	0.00	0.00					Dry, sunny and mild
	326.49		22/04/24 15:51		0.00	1.20	17.40	0.00	0.00					Dry, sunny and mild
	326.49		22/04/24 15:52		0.00	1.10	17.60	0.00	0.00					Dry, sunny and mild
BH22	333.84		31/01/24 09:00	966	0.00	0.00	19.00	0.00	0.00	0.00	0.00	0.69	333.15	Overcast, raining
	333.84		31/01/24 09:01		0.00	0.10	19.10	0.00	0.00					Overcast, raining
	333.84		31/01/24 09:02		0.00	0.10	19.10	0.00	0.00					Overcast, raining
	333.84		31/01/24 09:03		0.00	0.10	19.10	0.00	0.00					Overcast, raining
	333.84		31/01/24 09:04		0.00	0.10	19.00	0.00	0.00					Overcast, raining
	333.84		31/01/24 09:05		0.00	0.10	19.00	0.00	0.00					Overcast, raining
	333.84		28/02/24 09:00	960	0.00	0.00	19.60	0.00	0.00	0.00	0.00	0.83	333.01	Overcast, raining
	333.84		28/02/24 09:01		0.00	0.10	19.50	0.00	1.00					Overcast, raining
	333.84		28/02/24 09:02		0.00	0.10	19.50	0.00	0.00					Overcast, raining
	333.84		28/02/24 09:03		0.00	0.10	19.50	1.00	0.00					Overcast, raining
	333.84		28/02/24 09:04		0.00	0.10	19.50	0.00	1.00					Overcast, raining
	333.84		28/02/24 09:05		0.00	0.10	19.50	0.00	0.00		0.00			Overcast, raining
	333.84		25/03/24 14:22	960	0.00	0.00	17.80	0.00	0.00	-3.00	0.00	0.85	332.99	Overcast, occasional snow
	333.84		25/03/24 14:23		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	333.84		25/03/24 14:24		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	333.84		25/03/24 14:25		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	333.84		25/03/24 14:26		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	333.84		25/03/24 14:27		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	333.84		23/04/24 12:45	988	0.00	1.30	18.70	0.00	0.00	0.00	0.00	1.90	331.94	Dry, overcast and cool
	333.84		23/04/24 12:46		0.00	1.90	17.10	0.00	0.00					Dry, overcast and cool
	333.84		23/04/24 12:47		0.00	1.90	17.10	0.00	0.00					Dry, overcast and cool
	333.84		23/04/24 12:48		0.00	1.80	17.30	0.00	0.00					Dry, overcast and cool
	333.84		23/04/24 12:49		0.00	1.80	17.50	0.00	0.00					Dry, overcast and cool
	333.84		23/04/24 12:50		0.00	1.80	17.60	0.00	0.00					Dry, overcast and cool
BH23	316.00		12/01/23 00:00									0.30	315.70	
	316.00		08/12/23 00:00									0.25	315.75	
	316.00		15/12/23 00:00									0.00	316.00	
	316.00		19/12/23 00:00									0.06	315.94	
	316.00		01/02/24 09:00	984	0.00	0.00	19.20	0.00	0.00	0.00	0.00	0.00	316.00	Dry, Overcast
	316.00		01/02/24 09:01		0.00	0.00	19.30	0.00	0.00					Dry, Overcast
	316.00		01/02/24 09:02		0.00	0.00	19.20	0.00	0.00					Dry, Overcast
	316.00		01/02/24 09:03		0.00	0.00	19.20	0.00	0.00					Dry, Overcast

Chk & App <b>FMR</b>	Originator <b>JMcM</b>	Title: <b>RESULTS OF GAS AND WATER LEVEL MONITORING IN STANDPIPES</b>		Fig No: <b>E2</b>
	Status <b>Final</b>			Sheet 5 of 7



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission  
 Engineer: Jacobs

\* Water level measurements taken from ground level.

Borehole No.	Surveyed Level (m OD)	Depth to Base of Standpipe (m)	Date	Atmospheric Pressure (mBar)	Gas Composition					Differential Pressure (Pa)	Flow (l/hr)	Depth to Water (m) (mBGL)	Depth (mOD)	Remarks
					CH <sub>4</sub> (%vol)	CO <sub>2</sub> (%vol)	O <sub>2</sub> (%vol)	H <sub>2</sub> S (ppm)	CO (ppm)					
BH23	316.00		01/02/24 09:04		0.00	0.00	19.20	0.00	0.00					Dry, Overcast
	316.00		01/02/24 09:05		0.00	0.00	19.20	0.00	0.00					Dry, Overcast
	316.00		28/02/24 09:00	966	0.00	0.10	20.20	0.00	1.00	5.00	1.50	0.21	315.79	Overcast, raining
	316.00		28/02/24 09:01		0.00	0.10	19.70	0.00	2.00					Overcast, raining
	316.00		28/02/24 09:02		0.00	0.10	19.70	0.00	1.00					Overcast, raining
	316.00		28/02/24 09:03		0.00	0.10	19.70	1.00	2.00					Overcast, raining
	316.00		28/02/24 09:04		0.00	0.10	19.60	1.00	1.00					Overcast, raining
	316.00		28/02/24 09:05		0.00	0.10	19.60	0.00	3.00		1.10			Overcast, raining
	316.00		26/03/24 09:37	957	0.00	0.00	17.70	0.00	0.00	0.00	0.00	0.17	315.83	Overcast, occasional snow
	316.00		26/03/24 09:38		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	316.00		26/03/24 09:39		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	316.00		26/03/24 09:40		0.00	0.00	17.70	0.00	0.00					Overcast, occasional snow
	316.00		26/03/24 09:41		0.00	0.00	17.60	0.00	0.00					Overcast, occasional snow
	316.00		26/03/24 09:42		0.00	0.00	17.60	0.00	0.00					Overcast, occasional snow
	316.00		22/04/24 17:04	991	0.00	0.40	18.70	0.00	0.00	0.00	6.60	0.18	315.82	Dry, sunny and mild
	316.00		22/04/24 17:05		0.00	0.40	19.30	0.00	0.00					Dry, sunny and mild
	316.00		22/04/24 17:06		0.00	0.50	19.20	0.00	0.00					Dry, sunny and mild
	316.00		22/04/24 17:07		0.00	0.50	19.10	0.00	0.00					Dry, sunny and mild
	316.00		22/04/24 17:08		0.00	0.50	19.00	0.00	0.00					Dry, sunny and mild
	316.00		22/04/24 17:09		0.00	0.50	19.00	0.00	0.00		-0.10			Dry, sunny and mild
BH25	332.05		31/01/24 09:00	966	0.00	0.10	19.20	0.00	0.00	0.00	0.00	0.16	331.89	Overcast, raining
	332.05		31/01/24 09:01		0.00	0.10	19.30	0.00	1.00					Overcast, raining
	332.05		31/01/24 09:02		0.00	0.10	19.30	0.00	1.00					Overcast, raining
	332.05		31/01/24 09:03		0.00	0.10	19.30	0.00	0.00					Overcast, raining
	332.05		31/01/24 09:04		0.00	0.10	19.30	0.00	0.00					Overcast, raining
	332.05		31/01/24 09:05		0.00	0.10	19.20	0.00	0.00					Overcast, raining
	332.05		28/02/24 09:00	961	0.00	0.00	19.30	0.00	1.00	7.00	1.60	0.20	331.85	Overcast, raining
	332.05		28/02/24 09:01		0.00	0.10	19.50	0.00	0.00					Overcast, raining
	332.05		28/02/24 09:02		0.00	0.10	19.40	0.00	0.00					Overcast, raining
	332.05		28/02/24 09:03		0.00	0.10	19.40	0.00	0.00					Overcast, raining
	332.05		28/02/24 09:04		0.00	0.10	19.40	0.00	0.00					Overcast, raining
	332.05		28/02/24 09:05		0.00	0.10	19.40	0.00	1.00		1.60			Overcast, raining
	332.05		25/03/24 14:41	960	0.00	0.00	17.80	0.00	0.00	-3.00	-0.40	0.18	331.87	Overcast, occasional snow
	332.05		25/03/24 14:42		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	332.05		25/03/24 14:43		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	332.05		25/03/24 14:44		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	332.05		25/03/24 14:45		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	332.05		25/03/24 14:46		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	332.05		23/04/24 13:00	987	0.00	1.20	18.80	0.00	0.00	0.00	0.00	0.27	331.78	Dry, overcast and cool
	332.05		23/04/24 13:01		0.00	1.90	17.10	0.00	0.00					Dry, overcast and cool
	332.05		23/04/24 13:02		0.00	1.80	17.10	0.00	0.00					Dry, overcast and cool
	332.05		23/04/24 13:03		0.00	1.80	17.20	0.00	0.00					Dry, overcast and cool
	332.05		23/04/24 13:04		0.00	1.80	17.40	0.00	0.00					Dry, overcast and cool
	332.05		23/04/24 13:05		0.00	1.80	17.60	0.00	0.00					Dry, overcast and cool

Style: SPIPE MONITORING File: P:\GINTW\PROJECTS\26560.GPJ Printed: 23/05/2024 11:56:09 Reaburn Drilling and Geotechnical Whistler Rd, Hamilton ML3 OHP Tel: 01898-711177 E-mail: enquiries@reaburndrilling.com

Originator	Title:			Fig No:
JMcM Chk & App FMR	Status Final	<b>RESULTS OF GAS AND WATER LEVEL MONITORING IN STANDPIPES</b>		E2 Sheet 6 of 7



Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission  
 Engineer: Jacobs

\* Water level measurements taken from ground level.

Style: SPIPE MONITORING File: P:\GINTW\PROJECTS\26560.GPJ Printed: 23/05/2024 11:56:09 Raeburn Drilling and Geotechnical Whistleberry Rd, Hamilton ML3 QHP Tel: 01898-711177 E-mail: enquiries@raeburndrilling.com

Borehole No.	Surveyed Level (m OD)	Depth to Base of Standpipe (m)	Date	Atmospheric Pressure (mBar)	Gas Composition					Differential Pressure (Pa)	Flow (l/hr)	Depth to Water (m) (mBGL)	Depth (mOD)	Remarks
					CH <sub>4</sub> (%vol)	CO <sub>2</sub> (%vol)	O <sub>2</sub> (%vol)	H <sub>2</sub> S (ppm)	CO (ppm)					
BH26	315.06		24/11/23 00:00								0.30	314.76		
	315.06		01/12/23 00:00								0.33	314.73		
	315.06		08/12/23 00:00								0.51	314.55		
	315.06		15/12/23 00:00								0.80	314.26		
	315.06		19/12/23 00:00								0.75	314.31		
	315.06		12/01/24 00:00								0.47	314.59		
	315.06		01/02/24 00:00										Gas valve submerged	
	315.06		28/02/24 00:00										Gas valve submerged	
	315.06		25/03/24 00:00										Gas valve submerged	
	315.06		22/04/24 09:00	994	0.00	0.10	19.60	0.00	0.00	0.00	0.00		Dry, sunny and mild	
	315.06		22/04/24 09:01										Test terminated due to water ingress	
BH27	331.69		12/01/23 00:00								0.16	331.53		
	331.69		19/12/23 00:00								0.34	331.35		
	331.69		09/01/24 00:00								0.43	331.26		
	331.69		01/02/24 09:00	986	0.00	0.00	18.90	0.00	0.00	0.00	0.40	0.17	331.52	Dry, Overcast
	331.69		01/02/24 09:01		0.00	0.00	19.00	0.00	0.00					Dry, Overcast
	331.69		01/02/24 09:02		0.00	0.00	19.20	0.00	1.00					Dry, Overcast
	331.69		01/02/24 09:03		0.00	0.00	19.00	0.00	0.00					Dry, Overcast
	331.69		01/02/24 09:04		0.00	0.00	19.10	0.00	0.00					Dry, Overcast
	331.69		01/02/24 09:05		0.00	0.00	19.00	0.00	1.00					Dry, Overcast
	331.69		28/02/24 09:00	962	0.00	0.00	19.60	0.00	0.00	0.00	0.00	0.19	331.50	Overcast, raining
	331.69		28/02/24 09:01		0.00	0.00	19.50	0.00	0.00					Overcast, raining
	331.69		28/02/24 09:02		0.00	0.00	19.50	0.00	0.00					Overcast, raining
	331.69		28/02/24 09:03		0.00	0.00	19.50	0.00	1.00					Overcast, raining
	331.69		28/02/24 09:04		0.00	0.10	19.50	0.00	0.00					Overcast, raining
	331.69		28/02/24 09:05		0.00	0.10	19.50	0.00	0.00		0.00			Overcast, raining
	331.69		25/03/24 14:05	960	0.00	0.00	17.80	0.00	0.00	-3.00	-0.40	0.24	331.45	Overcast, occasional snow
	331.69		25/03/24 14:06		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	331.69		25/03/24 14:07		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	331.69		25/03/24 14:08		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	331.69		25/03/24 14:09		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	331.69		25/03/24 14:10		0.00	0.00	17.80	0.00	0.00					Overcast, occasional snow
	331.69		23/04/24 12:30	989	0.00	1.30	18.60	0.00	0.00	0.00	-17.10	0.29	331.40	Dry, overcast and cool
	331.69		23/04/24 12:31		0.00	2.00	17.00	0.00	0.00					Dry, overcast and cool
	331.69		23/04/24 12:32		0.00	1.90	17.10	0.00	0.00					Dry, overcast and cool
	331.69		23/04/24 12:33		0.00	1.90	17.20	0.00	0.00					Dry, overcast and cool
	331.69		23/04/24 12:34		0.00	1.90	17.40	0.00	0.00					Dry, overcast and cool
	331.69		23/04/24 12:35		0.00	1.80	17.50	0.00	0.00		0.00			Dry, overcast and cool

Originator	Title:		<b>RESULTS OF GAS AND WATER LEVEL MONITORING IN STANDPIPES</b>	Fig No:
Chk & App <b>FMR</b>	JMCM Status <b>Final</b>			







Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

Style: APPENDIX A File: P:\GINTWPROJECTS\26560.GPJ Printed: 05/02/2024 11:14:41 Raeburn Drilling and Geotechnical Whisteberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

APPENDIX F1  
GEOTECHNICAL TESTING - SOILS







Site: LT521 FASNAKYLE 400KV SUBSTATION

Contract No: 26560

Client: SSEN Transmission

Engineer: Jacobs

**TEST**

**STANDARD**

**CLASSIFICATION TESTS**

Determination of water content	BS EN ISO 17892-1:2014
Determination of liquid limit	BS 1377 : 1990 : Part 2 : 4.3 and 4.4
Determination of liquid and plastic limits	BS EN ISO 17892-12:2018
Determination of bulk density	BS EN ISO 17892-2:2014
Determination of particle density	BS EN ISO 17892-3:2016
Determination of particle size distribution	BS EN ISO 17892-4:2016

**CHEMICAL TESTS**

Determination of organic matter content	BS 1377 : 1990 : Part 3 : 3.4
Determination of mass loss on ignition	BS 1377 : 1990 : Part 3 : 4.3
Determination of sulphate content of soil and groundwater	BS 1377 : 1990 : Part 3 : 5.2, 5.3 and 5.5
Determination of chloride content	BS 1377 : 1990 : Part 3 : 7.2 and 7.3
Determination of pH value	BS 1377 : 1990 : Part 3 : 9.5

**COMPACTION-RELATED TESTS**

Determination of dry density/moisture content relationship	BS 1377 : 1990 : Part 4 : 3.3 to 3.6
Determination of moisture condition value (MCV)	SDD Tech Memo SH7/83; SDD Appls Guide No.1 Rev. 1989
Determination of California Bearing Ratio (CBR)	BS 1377 : 1990 : Part 4 : 7.4

**CONSOLIDATION AND STRENGTH TESTS**

Incremental loading oedometer test	BS EN ISO 17892-5:2017
Unconfined compression test	BS EN ISO 17892-7:2018
Unconsolidated undrained triaxial test	BS EN ISO 17892-8:2018
Consolidated triaxial compression tests on water saturated soils	BS EN ISO 17892-9:2018
Lab Vane Tests	BS 1377 : 1990
Direct shear tests	BS EN ISO 17892-10:2019
Permeability tests	BS EN ISO 17892-11:2019
Fall cone test	BS EN ISO 17892-6:2017


**ROCK TESTS**

Determination of point load strength	ISRM Commission on Testing Methods, 1985
Determination of unconfined compressive strength	ASTM D7012-14
LA Abrasion Tests	BS EN 1097-2-2010 and BS 818 : Part 2 : 1990
Magnesium Soundness Tests	BS EN 1367-2
Slake durability	ISRM Suggested methods
Rock porosity / density	ISRM Suggested methods








Exploratory Hole No.	Depth (m)	Sample Type	Test	Reason	Instruction
TP20	0.50	B	LSB	Insufficient sample. Have approx 17kg of material. Require >30kg passing 20mm sieve to carry out test. Sample sent for PSD, Comp & TR.	Cancel Test
TP13	0.40	B	Thermal Resistivity	Insufficient material passing 20mm. Approx 1.5kg requires min 6kg	Combine with bulk samples at 0.00m
TP19	0.60	B	Thermal Resistivity	Insufficient material amount passing 20mm 1040g from 13kg Need 6kg minimum	Cancel test
TP28	1.00	B	Thermal Resistivity	Insufficient material amount, only 2Kg need a minimum of 6Kg passing 20mm	Combine with Bulk sample at 0.5m.
TP32	0.50	B	LSB	Insufficient sample. Have approx 25kg of material. Require >30kg passing 20mm sieve to carry out test. Sample sent for PSD, Comp & CBR.	Cancel Test
TP36A	0.50	B	Large Shearbox	Insufficient material. Need 30KG passing 20mm sieve.	Cancel test

	Site	LT521 FASNAKYLE 400KV SUBSTATION	Contract No <b>26560</b>
	Client	SSEN Transmission	
	Engineer	Jacobs	

Sample Identification				Lab Sample ID	Non Engineering Description	Water Content %
Exploratory Hole	Depth m	Sample Ref	Sample Type			
BH02	0.10		B	2013667	Brown very gravelly very silty very sandy PEAT. Gravel is fine to medium	338.0
BH12	0.50		B	2013669	Brown silty very gravelly SAND. Gravel is fine to coarse	39.5
BH17	0.50		D	2013177	Brown silty SAND with organic material	38.2
BH17	1.20-2.20		U	2013178	Dark brown fibrous PEAT	105.0
BH28	0.50		B	2013353	Dark brown fibrous PEAT	918.0
BH28	2.65		B	2013354	Dark brown fibrous PEAT	646.0
TP01	0.50		D	2013181	Dark brown fibrous PEAT	875.0
TP03	0.00-0.00		D	2013184	Dark brown fibrous PEAT	348.0
TP06	0.00-0.00		D	2012881	Brown fibrous PEAT	292.0
TP07	0.30		B	2013187	Brown slightly gravelly slightly sandy SILT. Gravel is fine to coarse	25.8
TP09	0.00-0.00		D	2013190	Dark brown fibrous PEAT	239.0
TP10	0.50		D	2012882	Brown fibrous PEAT	818.0
TP11	1.00		D	2013192	Dark brown fibrous PEAT	1353.0
TP13	0.30		D	2013196	Brown sandy SILT with organic material	102.0



Notes

Originator	Checked & Approved	<b>Determination of the Water Content</b> BS EN ISO 17892-1:2014	 <b>Figure F1</b>
TP	 05/03/2024		

	Site	LT521 FASNAKYLE 400KV SUBSTATION	Contract No <b>26560</b>
	Client	SSEN Transmission	
	Engineer	Jacobs	

Sample Identification				Lab Sample ID	Non Engineering Description	Water Content %
Exploratory Hole	Depth m	Sample Ref	Sample Type			
TP15	0.50		D	2013200	Brown fibrous PEAT	661.0
TP16	0.00-0.00		D	2013202	Brown gravelly silty SAND. Gravel is fine to coarse	19.3
TP17	1.00		D	2013206	Dark brown fibrous PEAT	1045.0
TP18	0.50		D	2012885	Brown fibrous PEAT	593.0
TP20	0.50		B	2012888	Brown silty very sandy fine to coarse GRAVEL with cobbles and organic matter	41.8
TP21	0.00-0.00		D	2012889	Brown fibrous PEAT	398.0
TP22	1.00		D	2012891	Brown fibrous PEAT	918.0
TP24	0.00-0.00		D	2012892	Brown fibrous PEAT	448.0
TP28	1.00		D	2012897	Brown silty very sandy fine to coarse GRAVEL	6.4
TP28	1.50		B	2012898	Brown silty SAND and GRAVEL with cobbles. Gravel is fine to coarse	7.3
TP28	2.50		D	2012899	Brown silty SAND and GRAVEL. Gravel is fine to coarse	10.7
TP32	0.50		B	2012902	Brown silty very sandy fine to coarse GRAVEL	12.7
TP36A	0.50		B	2013357	Brown silty SAND and GRAVEL with organic material. Gravel is fine to coarse	24.1
TP36A	0.50		D	2013356	Brown silty SAND and GRAVEL with organic material. Gravel is fine to coarse	27.2

Notes

Originator	Checked & Approved	<b>Determination of the Water Content</b> BS EN ISO 17892-1:2014	 <b>Figure F1</b>
TP	 05/03/2024		





Site LT521 FASNAKYLE 400KV SUBSTATION  
 Client SSEN Transmission  
 Engineer Jacobs

Contract No. 26560

Hole ID BH12  
 Sample Ref  
 Depth (m) 0.50  
 Sample Type B

Non Engineering Description : Brown silty very gravelly SAND. Gravel is fine to coarse

Preparation : Sample oven dried, Percentage retained on 425µm sieve measured by wet sieving



Sample was determined to be Non-Plastic after preparation  
 Liquid Limit was determined by mixing using increasing water content and 30° cone

**Results :**

As Received Water Content : (BS EN ISO 17892-1:2014) 39.5 %  
 Percentage retained on 425µm sieve : 37 %  
 Liquid Limit : 33 %  
 Plastic Limit : Non-Plastic %

Equivalent water content of material passing 425µm sieve : 62.7 %

Originator	Checked & Approved
NW	CD 05/03/2024

**Liquid Limit (Four Point Cone Penetrometer Method)  
 Plastic Limit, Plasticity Index & Liquidity Index**  
 BS EN ISO 17892-12:2018 Clause 5.3  
 BS EN ISO 17892-12:2018 Clause 5.5



Figure F2





Site LT521 FASNAKYLE 400KV SUBSTATION  
 Client SSEN Transmission  
 Engineer Jacobs

Contract No. 26560

Hole ID TP36A  
 Sample Ref  
 Depth (m) 0.50  
 Sample Type D

Non Engineering Description : Brown silty SAND and GRAVEL with organic material. Gravel is fine to coarse

Preparation : Sample oven dried, Percentage retained on 425µm sieve measured by wet sieving



Sample was determined to be Non-Plastic after preparation  
 Liquid Limit was determined by mixing using increasing water content and 30° cone

**Results :**

As Received Water Content : (BS EN ISO 17892-1:2014) 27.2 %  
 Percentage retained on 425µm sieve : 60 %  
 Liquid Limit : 34 %  
 Plastic Limit : Non-Plastic %

Equivalent water content of material passing 425µm sieve : 68.0 %

Originator	Checked & Approved
NW	CD 05/03/2024

**Liquid Limit (Four Point Cone Penetrometer Method)  
 Plastic Limit, Plasticity Index & Liquidity Index**  
 BS EN ISO 17892-12:2018 Clause 5.3  
 BS EN ISO 17892-12:2018 Clause 5.5



Figure F3



Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission

Hole BH02

Engineer Jacobs

Sample Ref

Depth (m) 0.10

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	100
37.5 mm	100
28.0 mm	100
20.0 mm	100
14.0 mm	98
10.0 mm	95
6.30 mm	86
5.00 mm	82
3.35 mm	76
2.00 mm	76
1.18 mm	74
630 µm	71
425 µm	66
300 µm	57
200 µm	52
150 µm	44
63 µm	32
20 µm	20
6 µm	13
2 µm	6

Non Engineering Description
Brown very gravelly very silty very sandy PEAT. Gravel is fine to medium

Sample Proportions - %	
Cobbles	0.0
Gravel	24.0
Sand	44.8
Silt	25.5
Clay	5.7
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	20
D60	0.34
D10	0.0038
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	89.5

Notes
Sedimentation sample not pre-treated

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
RF	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**

BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method  
BS EN ISO 17892-4 2016 Clause 5.4 - Pipette Method



Figure F4



Site	LT521 FASNAKYLE 400KV SUBSTATION	Contract No	<b>26560</b>
Client	SSEN Transmission	Hole	BH03
Engineer	Jacobs	Sample Ref	
		Depth (m)	0.60
		Sample Type	B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	89
37.5 mm	80
28.0 mm	70
20.0 mm	61
14.0 mm	59
10.0 mm	56
6.30 mm	51
5.00 mm	49
3.35 mm	47
2.00 mm	46
1.18 mm	44
630 µm	43
425 µm	40
300 µm	35
200 µm	30
150 µm	21
63 µm	11
20 µm	6
6 µm	3
2 µm	2

Non Engineering Description
Brown silty very sandy fine to coarse GRAVEL

Sample Proportions - %	
Cobbles	0.0
Gravel	53.9
Sand	35.8
Silt	7.9
Clay	2.4
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	63
D60	17
D10	0.053
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	320.8

Notes
Sample does not comply with BS EN ISO 17892-4 minimum mass requirements Sedimentation sample not pre-treated

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
RF	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**  
 BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method  
 BS EN ISO 17892-4 2016 Clause 5.4 - Pipette Method

**Figure F5**  
 Sheet 1 of 1





Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission

Hole BH12

Engineer Jacobs

Sample Ref

Depth (m) 0.50

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	91
50.0 mm	91
37.5 mm	90
28.0 mm	85
20.0 mm	81
14.0 mm	79
10.0 mm	77
6.30 mm	74
5.00 mm	71
3.35 mm	68
2.00 mm	64
1.18 mm	58
630 µm	52
425 µm	48
300 µm	43
200 µm	32
150 µm	23
63 µm	12
20 µm	7
6 µm	5
2 µm	2

Non Engineering Description
Brown silty very gravelly SAND. Gravel is fine to coarse

Sample Proportions - %	
Cobbles	9.4
Gravel	26.8
Sand	51.7
Silt	9.6
Clay	2.5
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	75
D60	1.4
D10	0.037
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	37.8

Notes
Sedimentation sample not pre-treated

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
RF	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**

BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method  
BS EN ISO 17892-4 2016 Clause 5.4 - Pipette Method



Figure F6



Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission

Hole BH14

Engineer Jacobs

Sample Ref

Depth (m) 0.20

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	86
37.5 mm	78
28.0 mm	77
20.0 mm	73
14.0 mm	73
10.0 mm	72
6.30 mm	70
5.00 mm	69
3.35 mm	68
2.00 mm	67
1.18 mm	65
630 µm	62
425 µm	60
300 µm	56
200 µm	42
150 µm	37
63 µm	26
20 µm	20
6 µm	14
2 µm	4

Non Engineering Description
Brown very silty SAND and GRAVEL with organic material. Gravel is fine to coarse

Sample Proportions - %	
Cobbles	0.0
Gravel	33.2
Sand	40.9
Silt	21.6
Clay	4.3
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	63
D60	0.42
D10	0.0038
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	110.5


Notes
Sample does not comply with BS EN ISO 17892-4 minimum mass requirements Sedimentation sample not pre-treated

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
JM	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**  
 BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method  
 BS EN ISO 17892-4 2016 Clause 5.4 - Pipette Method


**Figure F7**  
 Sheet 1 of 1



Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No **26560**

Client SSEN Transmission

Hole BH16

Engineer Jacobs

Sample Ref

Depth (m) 0.40

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	100
37.5 mm	100
28.0 mm	100
20.0 mm	99
14.0 mm	95
10.0 mm	90
6.30 mm	75
5.00 mm	67
3.35 mm	66
2.00 mm	65
1.18 mm	63
630 µm	58
425 µm	52
300 µm	44
200 µm	34
150 µm	22
63 µm	9

Non Engineering Description
Brown silty very gravelly SAND. Gravel is fine to coarse

Sample Proportions - %	
Cobbles	0.0
Gravel	34.6
Sand	56.4
Silt & Clay	9.0
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	28
D60	0.79
D10	0.067
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	11.8

Notes

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
RF	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**  
BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method



Figure F8



Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission

Hole BH18

Engineer Jacobs

Sample Ref

Depth (m) 0.60

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	96
50.0 mm	96
37.5 mm	92
28.0 mm	88
20.0 mm	84
14.0 mm	78
10.0 mm	75
6.30 mm	70
5.00 mm	67
3.35 mm	63
2.00 mm	60
1.18 mm	56
630 µm	51
425 µm	48
300 µm	45
200 µm	38
150 µm	30
63 µm	17
20 µm	10
6 µm	5
2 µm	2

Non Engineering Description
Brown silty SAND and GRAVEL with cobbles and pockets of clay. Gravel is fine to coarse

Sample Proportions - %	
Cobbles	4.0
Gravel	35.9
Sand	43.5
Silt	14.5
Clay	2.1
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	75
D60	2.0
D10	0.018
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	111.1

Notes
Sedimentation sample not pre-treated

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
MC	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**

BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method  
BS EN ISO 17892-4 2016 Clause 5.4 - Pipette Method



Figure F9



Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission

Hole BH18

Engineer Jacobs

Sample Ref

Depth (m) 2.30

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	100
37.5 mm	100
28.0 mm	100
20.0 mm	100
14.0 mm	98
10.0 mm	90
6.30 mm	80
5.00 mm	75
3.35 mm	73
2.00 mm	70
1.18 mm	65
630 µm	53
425 µm	44
300 µm	35
200 µm	27
150 µm	20
63 µm	15
20 µm	8
6 µm	4
2 µm	2

Non Engineering Description
Brown silty very gravelly SAND. Gravel is fine to medium

Sample Proportions - %	
Cobbles	0.0
Gravel	29.9
Sand	55.8
Silt	12.6
Clay	1.7
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	20
D60	0.91
D10	0.029
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	31.4

Notes
Sedimentation sample not pre-treated

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
RF	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**

BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method  
BS EN ISO 17892-4 2016 Clause 5.4 - Pipette Method



Figure F10



Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission

Hole BH24A

Engineer Jacobs

Sample Ref

Depth (m) 1.00

Sample Type B

Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	100
37.5 mm	100
28.0 mm	97
20.0 mm	94
14.0 mm	91
10.0 mm	88
6.30 mm	85
5.00 mm	83
3.35 mm	80
2.00 mm	77
1.18 mm	74
630 µm	70
425 µm	68
300 µm	65
200 µm	57
150 µm	49
63 µm	34
20 µm	16
6 µm	11
2 µm	6

**Non Engineering Description**


Brown very gravelly very silty SAND with cobbles and pockets of clay. Gravel is fine to coarse

Sample Proportions - %	
Cobbles	0.0
Gravel	23.4
Sand	43.5
Silt	26.6
Clay	6.5
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	38
D60	0.23
D10	0.0044
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	52.3

**Notes**

Sedimentation sample not pre-treated

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
SG	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**  
 BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method  
 BS EN ISO 17892-4 2016 Clause 5.4 - Pipette Method



Figure F11



Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission

Hole BH27

Engineer Jacobs

Sample Ref

Depth (m) 1.20

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	100
37.5 mm	100
28.0 mm	100
20.0 mm	98
14.0 mm	90
10.0 mm	71
6.30 mm	51
5.00 mm	41
3.35 mm	39
2.00 mm	36
1.18 mm	31
630 µm	27
425 µm	21
300 µm	15
200 µm	10
150 µm	8
63 µm	6

Non Engineering Description
Brown silty very sandy fine to coarse GRAVEL

Sample Proportions - %	
Cobbles	0.0
Gravel	64.5
Sand	29.5
Silt & Clay	6.0
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	38
D60	7.8
D10	0.19
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	41.1

Notes

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
RF	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**  
BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method



Figure F12



Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No **26560**

Client SSEN Transmission

Hole BH28

Engineer Jacobs

Sample Ref

Depth (m) 3.95

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	100
37.5 mm	100
28.0 mm	100
20.0 mm	100
14.0 mm	91
10.0 mm	70
6.30 mm	54
5.00 mm	49
3.35 mm	46
2.00 mm	42
1.18 mm	36
630 µm	30
425 µm	23
300 µm	14
200 µm	9
150 µm	4
63 µm	2

Non Engineering Description
Grey slightly silty very sandy fine to coarse GRAVEL

Sample Proportions - %	
Cobbles	0.0
Gravel	58.2
Sand	40.0
Silt & Clay	1.8
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	20
D60	7.5
D10	0.22
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	34.1

Notes

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
RF	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**  
BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method



Figure F13





Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission

Hole TP05

Engineer Jacobs

Sample Ref

Depth (m) 0.50

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	88
37.5 mm	83
28.0 mm	79
20.0 mm	73
14.0 mm	72
10.0 mm	70
6.30 mm	69
5.00 mm	67
3.35 mm	64
2.00 mm	60
1.18 mm	54
630 µm	48
425 µm	40
300 µm	31
200 µm	24
150 µm	19
63 µm	17
20 µm	8
6 µm	4
2 µm	2

Non Engineering Description
Brown silty SAND and GRAVEL. Gravel is fine to coarse

Sample Proportions - %	
Cobbles	0.0
Gravel	39.9
Sand	44.1
Silt	13.6
Clay	2.3
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	63
D60	2.0
D10	0.026
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	76.9

Notes
Sample does not comply with BS EN ISO 17892-4 minimum mass requirements Sedimentation sample not pre-treated

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
JM	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**  
 BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method  
 BS EN ISO 17892-4 2016 Clause 5.4 - Pipette Method

**Figure F14**  
 Sheet 1 of 1



Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission

Hole TP10

Engineer Jacobs

Sample Ref

Depth (m) 1.50

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	91
37.5 mm	84
28.0 mm	76
20.0 mm	64
14.0 mm	55
10.0 mm	49
6.30 mm	44
5.00 mm	42
3.35 mm	39
2.00 mm	37
1.18 mm	35
630 µm	33
425 µm	30
300 µm	27
200 µm	21
150 µm	15
63 µm	8

Non Engineering Description
Brown silty very sandy fine to coarse GRAVEL

Sample Proportions - %	
Cobbles	0.0
Gravel	62.6
Sand	29.5
Silt & Clay	7.8
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	63
D60	17
D10	0.081
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	209.9

Notes

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
MC	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**  
BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method



Figure F15



Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission

Hole TP12

Engineer Jacobs

Sample Ref

Depth (m) 0.50

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	100
37.5 mm	96
28.0 mm	91
20.0 mm	87
14.0 mm	75
10.0 mm	68
6.30 mm	64
5.00 mm	61
3.35 mm	60
2.00 mm	58
1.18 mm	54
630 µm	49
425 µm	42
300 µm	28
200 µm	19
150 µm	10
63 µm	4

Non Engineering Description
Brown slightly silty SAND and GRAVEL. Gravel is fine to coarse

Sample Proportions - %	
Cobbles	0.0
Gravel	42.5
Sand	53.4
Silt & Clay	4.1
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	50
D60	3.3
D10	0.14
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	23.6

Notes

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
RF	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**  
BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method



Figure F16



Site	LT521 FASNAKYLE 400KV SUBSTATION	Contract No	<b>26560</b>
Client	SSEN Transmission	Hole	TP14
Engineer	Jacobs	Sample Ref	
		Depth (m)	0.50
		Sample Type	B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	85
63.0 mm	85
50.0 mm	79
37.5 mm	74
28.0 mm	67
20.0 mm	58
14.0 mm	56
10.0 mm	52
6.30 mm	47
5.00 mm	45
3.35 mm	42
2.00 mm	38
1.18 mm	33
630 µm	26
425 µm	19
300 µm	12
200 µm	7
150 µm	4
63 µm	3

Non Engineering Description
Brwn slightly silty SAND and GRAVEL with cobbles. Gravel is fine to coarse

Sample Proportions - %	
Cobbles	15.1
Gravel	46.6
Sand	35.4
Silt & Clay	2.8
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	90
D60	21
D10	0.26
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	80.8

Notes

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved	<b>PARTICLE SIZE DISTRIBUTION</b> BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method	<b>Figure F17</b>
JM	 05/03/2024		



Site	LT521 FASNAKYLE 400KV SUBSTATION	Contract No	<b>26560</b>
Client	SSEN Transmission	Hole	TP16
Engineer	Jacobs	Sample Ref	
		Depth (m)	0.50
		Sample Type	B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	94
50.0 mm	91
37.5 mm	90
28.0 mm	89
20.0 mm	87
14.0 mm	82
10.0 mm	73
6.30 mm	60
5.00 mm	55
3.35 mm	51
2.00 mm	47
1.18 mm	44
630 µm	37
425 µm	31
300 µm	23
200 µm	16
150 µm	10
63 µm	4

Non Engineering Description
Briwn slightly silty SAND and GRAVEL with cobbles. Gravel is fine to coarse

Sample Proportions - %	
Cobbles	6.0
Gravel	46.5
Sand	43.5
Silt & Clay	4.0
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	75
D60	6.4
D10	0.15
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	42.7

Notes

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved	<b>PARTICLE SIZE DISTRIBUTION</b> BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method	<b>Figure F18</b>
RF	 05/03/2024		



Site	LT521 FASNAKYLE 400KV SUBSTATION	Contract No	<b>26560</b>
Client	SSEN Transmission	Hole	TP20
Engineer	Jacobs	Sample Ref	
		Depth (m)	0.50
		Sample Type	B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	90
50.0 mm	84
37.5 mm	80
28.0 mm	75
20.0 mm	70
14.0 mm	58
10.0 mm	53
6.30 mm	49
5.00 mm	47
3.35 mm	44
2.00 mm	42
1.18 mm	40
630 µm	37
425 µm	34
300 µm	29
200 µm	22
150 µm	17
63 µm	10

Non Engineering Description
Brown silty very sandy fine to coarse GRAVEL with cobbles and organic matter

Sample Proportions - %	
Cobbles	9.7
Gravel	47.9
Sand	32.4
Silt & Clay	9.9
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	75
D60	15
D10	0.064
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	234.4

Notes

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved	<b>PARTICLE SIZE DISTRIBUTION</b> BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method	<b>Figure F19</b>
SG	 05/03/2024		



Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission

Hole TP25

Engineer Jacobs

Sample Ref

Depth (m) 0.50

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	87
75.0 mm	87
63.0 mm	82
50.0 mm	78
37.5 mm	73
28.0 mm	69
20.0 mm	66
14.0 mm	57
10.0 mm	53
6.30 mm	51
5.00 mm	51
3.35 mm	50
2.00 mm	49
1.18 mm	48
630 µm	45
425 µm	42
300 µm	37
200 µm	28
150 µm	18
63 µm	6

Non Engineering Description
Brown silty SAND and GRAVEL with cobbles. Gravel is fine to coarse

Sample Proportions - %	
Cobbles	17.9
Gravel	33.0
Sand	43.2
Silt & Clay	5.9
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	125
D60	16
D10	0.084
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	190.5

Notes

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
SG	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**  
BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method



Figure F20



Site	LT521 FASNAKYLE 400KV SUBSTATION	Contract No	<b>26560</b>
Client	SSEN Transmission	Hole	TP28
Engineer	Jacobs	Sample Ref	
		Depth (m)	1.50
		Sample Type	B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	90
63.0 mm	87
50.0 mm	82
37.5 mm	75
28.0 mm	69
20.0 mm	64
14.0 mm	55
10.0 mm	51
6.30 mm	49
5.00 mm	47
3.35 mm	45
2.00 mm	43
1.18 mm	41
630 µm	39
425 µm	37
300 µm	33
200 µm	25
150 µm	18
63 µm	7

Non Engineering Description
Brown silty SAND and GRAVEL with cobbles. Gravel is fine to coarse

Sample Proportions - %	
Cobbles	13.0
Gravel	43.8
Sand	36.2
Silt & Clay	7.0
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	90
D60	17
D10	0.079
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	215.2

Notes

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved	<b>PARTICLE SIZE DISTRIBUTION</b> BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method	<b>Figure F21</b>
MC	 05/03/2024		





Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No **26560**

Client SSEN Transmission

Hole TP29

Engineer Jacobs

Sample Ref

Depth (m) 1.00

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	96
37.5 mm	76
28.0 mm	66
20.0 mm	63
14.0 mm	51
10.0 mm	47
6.30 mm	43
5.00 mm	41
3.35 mm	40
2.00 mm	38
1.18 mm	36
630 µm	32
425 µm	28
300 µm	23
200 µm	18
150 µm	14
63 µm	8

Non Engineering Description
Brown silty very sandy fine to coarse GRAVEL

Sample Proportions - %	
Cobbles	0.0
Gravel	62.2
Sand	29.5
Silt & Clay	8.3
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	63
D60	18
D10	0.082
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	219.5

Notes
Sample does not comply with BS EN ISO 17892-4 minimum mass requirements

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
Silt			Sand			Gravel				



Originator	Checked & Approved
MC	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**  
BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method



Figure F22



Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission

Hole TP32

Engineer Jacobs

Sample Ref

Depth (m) 0.50

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	100
37.5 mm	94
28.0 mm	90
20.0 mm	86
14.0 mm	64
10.0 mm	58
6.30 mm	50
5.00 mm	48
3.35 mm	45
2.00 mm	43
1.18 mm	41
630 µm	37
425 µm	33
300 µm	28
200 µm	19
150 µm	12
63 µm	6

Non Engineering Description
Brown silty very sandy fine to coarse GRAVEL

Sample Proportions - %	
Cobbles	0.0
Gravel	56.7
Sand	37.4
Silt & Clay	5.9
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	50
D60	11
D10	0.11
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	100.0

Notes

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
Silt			Sand			Gravel				



Originator	Checked & Approved
MC	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**  
BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method



Figure F23



Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission

Hole TP33

Engineer Jacobs

Sample Ref

Depth (m) 0.50

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	79
37.5 mm	75
28.0 mm	66
20.0 mm	59
14.0 mm	58
10.0 mm	55
6.30 mm	51
5.00 mm	49
3.35 mm	47
2.00 mm	42
1.18 mm	37
630 µm	30
425 µm	23
300 µm	16
200 µm	11
150 µm	6
63 µm	2

Non Engineering Description
Brown slightly silty very sandy fine to coarse GRAVEL

Sample Proportions - %	
Cobbles	0.0
Gravel	57.9
Sand	39.6
Silt & Clay	2.4
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	63
D60	21
D10	0.19
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	110.5

Notes
Sample does not comply with BS EN ISO 17892-4 minimum mass requirements

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
JM	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**  
BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method



Figure F24



Site	LT521 FASNAKYLE 400KV SUBSTATION	Contract No	<b>26560</b>
Client	SSEN Transmission	Hole	TP34
Engineer	Jacobs	Sample Ref	
		Depth (m)	0.50
		Sample Type	B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	100
37.5 mm	93
28.0 mm	87
20.0 mm	80
14.0 mm	66
10.0 mm	57
6.30 mm	51
5.00 mm	45
3.35 mm	43
2.00 mm	40
1.18 mm	38
630 µm	35
425 µm	31
300 µm	26
200 µm	20
150 µm	15
63 µm	9

Non Engineering Description
Brown silty very sandy fine to coarse GRAVEL

Sample Proportions - %	
Cobbles	0.0
Gravel	59.6
Sand	31.1
Silt & Clay	9.2
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	50
D60	11
D10	0.071
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	154.9

Notes

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved	<b>PARTICLE SIZE DISTRIBUTION</b> BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method	<b>Figure F25</b>
SM	 05/03/2024		



Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission

Hole TP36A

Engineer Jacobs

Sample Ref

Depth (m) 0.50

Sample Type B


Particle Size	% Passing
125.0 mm	100
90.0 mm	100
75.0 mm	100
63.0 mm	100
50.0 mm	89
37.5 mm	86
28.0 mm	83
20.0 mm	80
14.0 mm	75
10.0 mm	70
6.30 mm	67
5.00 mm	65
3.35 mm	62
2.00 mm	59
1.18 mm	53
630 µm	48
425 µm	40
300 µm	29
200 µm	19
150 µm	12
63 µm	8

Non Engineering Description
Brown silty SAND and GRAVEL with organic material. Gravel is fine to coarse

Sample Proportions - %	
Cobbles	0.0
Gravel	41.3
Sand	50.9
Silt & Clay	7.8
Particle Density - Assumed (Mg/m3)	2.65
Particle Diameter - mm	
D100	63
D60	2.4
D10	0.099
Uniformity Coefficient <small>(SHW series 600, Table 6/1, footnote 5)</small>	24.2

Notes
Sample does not comply with BS EN ISO 17892-4 minimum mass requirements

Clay	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	Cobbles
	Silt			Sand			Gravel			



Originator	Checked & Approved
JM	CD 05/03/2024

**PARTICLE SIZE DISTRIBUTION**  
BS EN ISO 17892-4 2016 Clause 5.2 - Sieving Method



Figure F26



Site LT521 FASNAKYLE 400KV SUBSTATION

Client SSEN Transmission

Engineer Jacobs

Contract No 26560


Hole TP20

Sample Ref

Depth (m) 0.50

Sample Type B

Non-standard test due to % retained on 20mm/37.5mm sieve



Non Engineering Description	Brown silty very sandy fine to coarse GRAVEL with cobbles and organic matter
Preparation	Oven dried
Test Method	4.5kg Rammer for soils with some coarse gravel-size particles
Samples Used	Single
Mass Retained on 37.5 mm Sieve	% 20
Mass Retained on 20.0 mm Sieve	% 30
Particle Density - Assumed	Mg/m³ 2.40
Natural Moisture Content	% 42
Maximum Dry Density	Mg/m³ 1.61
Optimum Moisture Content	% 16.4

Originator	Checked & Approved
SM	CD 05/03/2024

**Moisture Content / Dry Density Relationship**  
BS1377:Part 4:1990 Clause 3.6

**Figure F27**

Sheet 1 of 1



Site LT521 FASNAKYLE 400KV SUBSTATION

Client SSEN Transmission

Engineer Jacobs

Contract No 26560


Hole TP28

Sample Ref

Depth (m) 1.50

Sample Type B


Non-standard test due to % retained on 20mm/37.5mm sieve



Non Engineering Description	Brown silty SAND and GRAVEL with cobbles. Gravel is fine to coarse
Preparation	Oven dried
Test Method	4.5kg Rammer for soils with some coarse gravel-size particles
Samples Used	Single
Mass Retained on 37.5 mm Sieve	% 25
Mass Retained on 20.0 mm Sieve	% 36
Particle Density - Assumed	Mg/m³ 2.65
Natural Moisture Content	% 7.3
Maximum Dry Density	Mg/m³ 2.06
Optimum Moisture Content	% 7.7

Originator	Checked & Approved
RF	CD 05/03/2024

**Moisture Content / Dry Density Relationship**  
BS1377:Part 4:1990 Clause 3.6



**Figure F28**  
 Sheet 1 of 1



Site LT521 FASNAKYLE 400KV SUBSTATION  
 Client SSEN Transmission  
 Engineer Jacobs

Contract No 26560

Hole TP32  
 Sample Ref  
 Depth (m) 0.50  
 Sample Type B



Non Engineering Description	Brown silty very sandy fine to coarse GRAVEL
Preparation	Oven dried
Test Method	4.5kg Rammer for soils with some coarse gravel-size particles
Samples Used	Single
Mass Retained on 37.5 mm Sieve	% 6
Mass Retained on 20.0 mm Sieve	% 14
Particle Density - Assumed	Mg/m³ 2.65
Natural Moisture Content	% 13
Maximum Dry Density	Mg/m³ 1.96
Optimum Moisture Content	% 9.5

Originator	Checked & Approved
RF	CD 05/03/2024

**Moisture Content / Dry Density Relationship**  
 BS1377:Part 4:1990 Clause 3.6



Figure F29





Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission


Hole TP36A

Engineer Jacobs

Sample Ref

Depth (m) 0.50

Sample Type B



Non Engineering Description	Brown silty SAND and GRAVEL with organic material. Gravel is fine to coarse
Preparation	Oven dried
Test Method	4.5kg Rammer for soils with some coarse gravel-size particles
Samples Used	Single
Mass Retained on 37.5 mm Sieve	% 9
Mass Retained on 20.0 mm Sieve	% 19
Particle Density - Assumed	Mg/m³ 2.65
Natural Moisture Content	% 24
Maximum Dry Density	Mg/m³ 2.00
Optimum Moisture Content	% 9.4

Originator	Checked & Approved
RF	CD 05/03/2024

**Moisture Content / Dry Density Relationship**  
BS1377:Part 4:1990 Clause 3.6

**Figure F30**

Sheet 1 of 1



Site LT521 FASNAKYLE 400KV SUBSTATION

Contract No 26560

Client SSEN Transmission

Hole ID TP28

Engineer Jacobs

Sample No

Depth (m) 1.50

Sample Type B

**Non Engineering Description:** Brown silty SAND and GRAVEL with cobbles. Gravel is fine to coarse

**Preparation Details:**

Specimen was prepared at Natural Moisture Content

Compaction using 4.5kg compactive effort

Specimen Bulk Density 2.20 Mg/m<sup>3</sup>

Specimen Dry Density 2.01 Mg/m<sup>3</sup>

Mass of sample > 20 mm 36.0 %

Specimen Unsoaked

**Test Details:**

Surcharge: 2.0 kg

Seating Load: 250 N

Moisture Content: 9.4 %

**Base**

2.0 kg


250 N

9.5 %


CBR Value: 60.0 %

59.8 %

Top of Specimen Penetration (mm)



Base of Specimen Penetration (mm)



Non-standard test due to % retained on 20mm sieve

Originator

Checked & Approved

DW

CD  
05/03/2024

**CALIFORNIA BEARING RATIO**

BS1377 : Part 4 : Clause 7 : 1990



Figure No F31



Site LT521 FASNAKYLE 400KV SUBSTATION  
 Client SSEN Transmission  
 Engineer Jacobs

Contract No 26560  
 Hole ID TP32  
 Sample No  
 Depth (m) 0.50  
 Sample Type B

**Non Engineering Description:** Brown silty very sandy fine to coarse GRAVEL


**Preparation Details:**

Specimen was prepared at Natural Moisture Content  
 Compaction using 4.5kg compactive effort  
 Specimen Bulk Density 2.05 Mg/m<sup>3</sup>  
 Specimen Dry Density 1.75 Mg/m<sup>3</sup>  
 Mass of sample > 20 mm 13.6 %  
 Specimen Unsoaked


**Test Details:**

	Top	Base
Surcharge:	2.0 kg	2.0 kg
Seating Load:	10 N	10 N
Moisture Content:	17 %	17 %
CBR Value:	2.1 %	2.1 %

Top of Specimen Penetration (mm)



Base of Specimen Penetration (mm)



Non-standard test due to % retained on 20mm sieve

Originator	Checked & Approved	<b>CALIFORNIA BEARING RATIO</b> BS1377 : Part 4 : Clause 7 : 1990	<b>Figure No F32</b>
DW	CD 05/03/2024		



Site	LT521 FASNAKYLE 400KV SUBSTATION	Contract No	26560
Client	SSEN Transmission	Hole ID	TP36A
Engineer	Jacobs	Sample No	
		Depth (m)	0.50
		Sample Type	B

**Non Engineering Description:** Brown silty SAND and GRAVEL with organic material. Gravel is fine to coarse

**Preparation Details:**

Specimen was prepared at Natural Moisture Content

Compaction using 4.5kg compactive effort

Specimen Bulk Density 2.20 Mg/m<sup>3</sup>

Specimen Dry Density 1.79 Mg/m<sup>3</sup>

Mass of sample > 20 mm 20.0 %

Specimen Unsoaked

**Test Details:**

Surcharge: 2.0 kg

Seating Load: 50 N

Moisture Content: 23 %

**Base**

2.0 kg

50 N



24 %

CBR Value: 12.0 %

12.7 %

Top of Specimen Penetration (mm)

Base of Specimen Penetration (mm)



Originator	Checked & Approved
SM	CD 05/03/2024

**CALIFORNIA BEARING RATIO**  
BS1377 : Part 4 : Clause 7 : 1990



Figure No F33




Site LT521 FASNAKYLE 400KV SUBSTATION  
Client SSEN Transmission  
Engineer Jacobs

Contract No **26560**  
Hole ID BH17  
Sample Ref  
Depth 1.20-2.20  
Sample Type U

Non Engineering Description: Dark brown fibrous PEAT

Initial Water Content	110 %	Final Water Content	88.6 %
Initial Voids Ratio	2.877	Final Voids Ratio	2.094
Initial Bulk Density	1.44 Mg/m <sup>3</sup>	Specific Gravity	2.65 (assumed)
Initial Dry Density	0.68 Mg/m <sup>3</sup>	Degree of saturation	102 %
Specimen Dimensions	20.07mm x 74.70mm dia		
Laboratory temperature	20±2°C		

Pressure Range kPa	M <sub>v</sub> m <sup>2</sup> /MN	C <sub>v</sub> (t90) m <sup>2</sup> /year	C <sub>v</sub> (t50) m <sup>2</sup> /year	Voids ratio (e)	C <sub>sec</sub>
0 - 10	6.886	2.56	2.44	2.610	
10 - 20	3.462	0.81	0.91	2.485	
20 - 40	2.411	1.51	1.58	2.317	
40 - 80	2.024	1.38	1.47	2.049	
80 - 40	0.179	swelled	swelled	2.070	
40 - 20	0.378	swelled	swelled	2.094	



Originator	Checked & Approved
SG	CD 05/03/2024

**INCREMENTAL LOADING OEDOMETER TEST**  
BS EN ISO 17892-5:2017, Root time curve fitting



Figure No F34

**Specimen Details**

**Specimen Number**

**Application Pressure Stage**

**Shearing Stage**

**Peak Conditions:**

**Residual Conditions:**

**Shear Strength Parameters**


8  
40

**Shear Strength by Direct Shear (large shearbox)**



Figure F35

*Jar*



Shear Strength Parameters (linear tangent interpretation)


o

Shear Strength by Direct Shear (large shearbox)



Figure F35

*lar*




Shear Strength by Direct Shear (large shearbox)



Figure F35

*lar*







Shear Strength by Direct Shear (large shearbox)

*lar*



Figure F35





Shear Strength by Direct Shear (large shearbox)



Figure F35

*lar*





**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*Jan*





Contract No

																				Thermal Conductivity	Thermal Resistivity	
																				W/mK	mK/W	
																				1.68	0.59	
																				0.28	3.59	
																				U	U	

**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*dar*

**Figure  
F37**





**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*Jan*

																	Thermal Conductivity	Thermal Resistivity		
																		W/mK		mK/W
																		u	u	

SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS



**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*Jan*







Contract No

																Thermal Conductivity	Thermal Resistivity				
																		W/mK	mK/W		
																		1.39	0.74		
																		0.16	6.37		
																		u	u		

**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

Figure F39

*dar*



**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*Jan*





Contract No

																Thermal Conductivity	Thermal Resistivity			
																		W/mK	mK/W	
																		0.77	1.30	
																		0.14	7.20	
																		u	u	

**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

Figure  
F40

*dar*



**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*Jan*





Contract No

																		Thermal Conductivity	Thermal Resistivity							
																		W/mK	mK/W							
																								2.16	0.46	
																								0.31	3.17	
																								u	u	

SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS

Figure F41

*dar*



**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*Jan*





Contract No

																	Thermal Conductivity	Thermal Resistivity						
																					W/mK	mK/W		
																					0.55	1.77		
																					0.06	16.66		
																					u	u		

SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS

Figure F42

*dar*



**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*Jan*







Contract No

																	Thermal Conductivity	Thermal Resistivity						
																					W/mK	mK/W		
																					1.11	0.89		
																					0.19	5.22		
																					u	u		

SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS

Figure F43

*dar*





**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*Jan*

																	Thermal Conductivity	Thermal Resistivity			
																				W/mK	mK/W
																				0.59	1.68
																			0.04	22.25	
																	U	U			

SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS

*[Signature]*



**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*Jan*





Contract No

																Thermal Conductivity	Thermal Resistivity			
																W/mK	mK/W			
																	1.66	0.60		
																	0.24	4.15		

**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*[Signature]*

Figure F45



**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*Jan*





Contract No

																	Thermal Conductivity	Thermal Resistivity						
																					W/mK	mK/W		
																					1.16	0.85		
																					0.88	1.13		
																					u	u		

**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

Figure F46

*dar*



**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*Jan*







Contract No

																	Thermal Conductivity	Thermal Resistivity				
																				W/mK	mK/W	
																				1.38	0.72	
																				0.31	3.17	
																				u	u	

SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS

Figure F47

*[Handwritten signature]*



**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*Jan*





Contract No

																	Thermal Conductivity	Thermal Resistivity						
																					W/mK	mK/W		
																					0.27	3.71		
																					0.21	4.67		
																					u	u		

**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

Figure F48

*dar*



**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*Jan*





Contract No

																	Thermal Conductivity	Thermal Resistivity						
																					W/mK	mK/W		
																					0.32	3.09		
																					0.30	3.27		
																					u	u		

SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS

Figure F49

*dar*



**SUMMARY OF THERMAL CONDUCTIVITY / RESISTIVITY TESTS**

*Jan*



# DETS

## Certificate of Analysis

*Certificate Number* 23-29964-0

*Issued:*

*Client* Terra Tek  
62 Rochsolloch Road  
Airdrie  
ML6 9BG

*Our Reference* 23-29964-0

*Client Reference* ~ A15075-1

*Order No* ~ AL013848

*Contract Title* ~ (not supplied)

*Description* 8 Soil samples.

*Date Received* 20-Dec-23

*Date Started* 20-Dec-23

*Date Completed* 18-Mar-24

*Test Procedures* Identified by prefix DETSn (details on request).

**Notes** This report supersedes 23-29964, amendments made

Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.

*Approved By*



Kirk Bridgewood  
General Manager



## Summary of Chemical Analysis Soil Samples

Our Ref 23-29964-0

Client Ref ~ A15075-1

Contract Title ~

Lab No	2280028	2280029	2280030	2280031	2280032	2280033	2280034	2280035
Sample ID ~	TP10	TP18	TP19	TP21	TP22	TP24	TP26	TP22
Depth ~	0.50	0.50	0.50	0.00	0.50	0.00	1.00	1.00
Other ID ~	2012882	2012885	2012886	2012889	2012890	2012892	2012895	2012891
Sample Type ~	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL
Sampling Date ~	24/11/2023	23/11/2023	23/11/2023	23/11/2023	24/11/2023	22/11/2023	22/11/2023	24/11/2023
Sampling Time ~	n/s	n/s	n/s	n/s	n/s	n/s	n/s	n/s

Test	Method	LOD	Units						
<b>Inorganics</b>									
pH	DETSC 2008#		pH			4.5		3.9	4.2
Organic matter	DETSC 2002#	0.1	%	19	17		23	24	19
Sulphate Aqueous Extract as SO4 (2:1)	DETSC 2076#	10	mg/l			45		77	47
Sulphur as S, Total	DETSC 2320	0.01	%			0.06		0.35	0.59
Sulphate as SO4, Total	DETSC 2321#	0.01	%			0.12		0.26	0.27



## Information in Support of the Analytical Results

Our Ref 23-29964-0  
 Client Ref ~ A15075-1  
 Contract ~

### Containers Received & Deviating Samples

Lab No	Sample ID ~	Date Sampled ~	Containers Received	Holding time exceeded for tests	Inappropriate container for tests
2280028	TP10 0.50 SOIL	24/11/23	PT 500ml		
2280029	TP18 0.50 SOIL	23/11/23	PT 500ml		
2280030	TP19 0.50 SOIL	23/11/23	PT 500ml	Total Sulphur ICP (7 days), pH + Conductivity (7 days)	
2280031	TP21 0.00 SOIL	23/11/23	PT 500ml		
2280032	TP22 0.50 SOIL	24/11/23	PT 500ml	Total Sulphur ICP (7 days), pH + Conductivity (7 days)	
2280033	TP24 0.00 SOIL	22/11/23	PT 500ml		
2280034	TP26 1.00 SOIL	22/11/23	PT 500ml	Total Sulphur ICP (7 days), pH + Conductivity (7 days)	
2280035	TP22 1.00 SOIL	24/11/23	PT 500ml		

Key: P-Plastic T-Tub

DETS cannot be held responsible for the integrity of samples received whereby the laboratory did not undertake the sampling. In this instance samples received may be deviating. Deviating Sample criteria are based on British and International standards and laboratory trials in conjunction with the UKAS note 'Guidance on Deviating Samples'. All samples received are listed above. However, those samples that have additional comments in relation to hold time, inappropriate containers etc are deviating due to the reasons stated. This means that the analysis is accredited where applicable, but results may be compromised due to sample deviations. If no sampled date (soils) or date+time (waters) has been supplied then samples are deviating. However, if you are able to supply a sampled date (and time for waters) this will prevent samples being reported as deviating where specific hold times are not exceeded and where the container supplied is suitable.

### Soil Analysis Notes

Inorganic soil analysis was carried out on a dried sample, crushed to pass a 425µm sieve, in accordance with BS1377.

Organic soil analysis was carried out on an 'as received' sample. Organics results are corrected for moisture and expressed on a dry weight basis.

The Loss on Drying, used to express organics analysis on an air dried basis, is carried out at a temperature of 28°C +/-2°C.

### Disposal

From the issue date of this test certificate, samples will be held for the following times prior to disposal :-

Soils - 1 month, Liquids - 2 weeks, Asbestos (test portion) - 6 months

#### Key:

~ Sample details are provided by the client and can affect the validity of the results

\* -not accredited.

# -MCERTS (accreditation only applies if report carries the MCERTS logo).

\$ -subcontracted.

n/s -not supplied.

I/S -insufficient sample.

U/S -unsuitable sample.

t/f -to follow.

nd -not detected.

#### End of Report



# DETS

## Certificate of Analysis

*Certificate Number* 24-00916-0-1

*Issued:*

*Client* Terra Tek  
62 Rochsolloch Road  
Airdrie  
ML6 9BG

*Our Reference* 24-00916-0-1

*Client Reference* ~ A15075-2

*Order No* ~ (not supplied)

*Contract Title* ~ (not supplied)

*Description* 20 Soil samples.

*Date Received* 17-Jan-24

*Date Started* 17-Jan-24

*Date Completed* 18-Mar-24

*Test Procedures* Identified by prefix DETSn (details on request).

**Notes** This report supersedes 24-00916, amendments made

Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.

*Approved By*



Kirk Bridgewood  
General Manager



## Summary of Chemical Analysis Soil Samples

Our Ref 24-00916-0-1

Client Ref ~ A15075-2

Contract Title ~

Lab No	2287345	2287346	2287347	2287348	2287349	2287350	2287351	2287352	2287353	2287354	2287355
Sample ID ~	TP13	TP15	TP16	TP16	TP17	TP17	TP19	TP21	TP22	TP23	TP24
Depth ~	0.30	0.50	0.50	0.80	1.00	2.00	0.70	0.70	2.00	0.70	0.50
Other ID ~	2013196	2013200	2013203	2013205	2013206	2013207	2013210	2013211	2013212	2013213	2013214
Sample Type ~	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL
Sampling Date ~	29/11/2023	27/11/2023	27/11/2023	27/11/2023	27/11/2023	27/11/2023	23/11/2023	23/11/2023	24/11/2023	22/11/2023	22/11/2023
Sampling Time ~	n/s	n/s	n/s	n/s	n/s	n/s	n/s	n/s	n/s	n/s	n/s

Test	Method	LOD	Units											
<b>Inorganics</b>														
pH	DETSC 2008#		pH			6.3	7.0		5.5	5.6	5.5	5.5	6.5	5.4
Organic matter	DETSC 2002#	0.1	%	17	18			13						
Sulphate Aqueous Extract as SO4 (2:1)	DETSC 2076#	10	mg/l			24	26		27	< 10	12	27	11	< 10
Sulphur as S, Total	DETSC 2320	0.01	%			0.02	0.03		0.30	0.03	0.01	0.05	< 0.01	0.01
Sulphate as SO4, Total	DETSC 2321#	0.01	%			0.03	0.03		0.51	0.04	0.02	0.04	0.02	0.02

## Summary of Chemical Analysis Soil Samples

Our Ref 24-00916-0-1

Client Ref ~ A15075-2

Contract Title ~

Lab No	2287356	2287357	2287358	2287359	2287360	2287361	2287362	2287363	2287364
Sample ID ~	BH17	TP01	TP02	TP03	TP07	TP08	TP09	TP11	TP12
Depth ~	0.50	0.50	0.00	0.00	0.00	0.00	0.20	1.00	0.00
Other ID ~	2013177	2013181	2013183	2013184	2013186	2013188	2013191	2013192	2013193
Sample Type ~	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL
Sampling Date ~	30/11/2023	29/11/2023	29/11/2023	04/12/2023	29/11/2023	04/12/2023	28/11/2023	04/12/2023	29/11/2023
Sampling Time ~	n/s	n/s	n/s	n/s	n/s	n/s	n/s	n/s	n/s

Test	Method	LOD	Units									
<b>Inorganics</b>												
pH	DETSC 2008#		pH			4.3		4.5	4.6	4.5		4.3
Organic matter	DETSC 2002#	0.1	%	13	14		21				22	
Sulphate Aqueous Extract as SO4 (2:1)	DETSC 2076#	10	mg/l			47		22	37	13		15
Sulphur as S, Total	DETSC 2320	0.01	%									
Sulphate as SO4, Total	DETSC 2321#	0.01	%									

## Information in Support of the Analytical Results

Our Ref 24-00916-0-1  
 Client Ref ~ A15075-2  
 Contract ~

### Containers Received & Deviating Samples

Lab No	Sample ID ~	Date		Containers Received	Holding time exceeded for tests	Inappropriate container for tests
		Sampled ~				
2287345	TP13 0.30 SOIL	29/11/23		PT 500ml	Organic Matter (Manual) (28 days)	
2287346	TP15 0.50 SOIL	27/11/23		PT 500ml	Organic Matter (Manual) (28 days)	
2287347	TP16 0.50 SOIL	27/11/23		PT 500ml	Anions 2:1 (30 days), Total Sulphur ICP (7 days), Total Sulphate ICP (30 days), pH + Conductivity (7 days)	
2287348	TP16 0.80 SOIL	27/11/23		PT 500ml	Anions 2:1 (30 days), Total Sulphur ICP (7 days), Total Sulphate ICP (30 days), pH + Conductivity (7 days)	
2287349	TP17 1.00 SOIL	27/11/23		PT 500ml	Organic Matter (Manual) (28 days)	
2287350	TP17 2.00 SOIL	27/11/23		PT 500ml	Anions 2:1 (30 days), Total Sulphur ICP (7 days), Total Sulphate ICP (30 days), pH + Conductivity (7 days)	
2287351	TP19 0.70 SOIL	23/11/23		PT 500ml	Anions 2:1 (30 days), Total Sulphur ICP (7 days), Total Sulphate ICP (30 days), pH + Conductivity (7 days)	
2287352	TP21 0.70 SOIL	23/11/23		PT 500ml	Anions 2:1 (30 days), Total Sulphur ICP (7 days), Total Sulphate ICP (30 days), pH + Conductivity (7 days)	
2287353	TP22 2.00 SOIL	24/11/23		PT 500ml	Anions 2:1 (30 days), Total Sulphur ICP (7 days), Total Sulphate ICP (30 days), pH + Conductivity (7 days)	
2287354	TP23 0.70 SOIL	22/11/23		PT 500ml	Anions 2:1 (30 days), Total Sulphur ICP (7 days), Total Sulphate ICP (30 days), pH + Conductivity (7 days)	
2287355	TP24 0.50 SOIL	22/11/23		PT 500ml	Anions 2:1 (30 days), Total Sulphur ICP (7 days), Total Sulphate ICP (30 days), pH + Conductivity (7 days)	
2287356	BH17 0.50 SOIL	30/11/23		PT 500ml	Organic Matter (Manual) (28 days)	
2287357	TP01 0.50 SOIL	29/11/23		PT 500ml	Organic Matter (Manual) (28 days)	
2287358	TP02 0.00 SOIL	29/11/23		PT 500ml	Anions 2:1 (30 days), pH + Conductivity (7 days)	
2287359	TP03 0.00 SOIL	04/12/23		PT 500ml	Organic Matter (Manual) (28 days)	
2287360	TP07 0.00 SOIL	29/11/23		PT 500ml	Anions 2:1 (30 days), pH + Conductivity (7 days)	
2287361	TP08 0.00 SOIL	04/12/23		PT 500ml	Anions 2:1 (30 days), pH + Conductivity (7 days)	
2287362	TP09 0.20 SOIL	28/11/23		PT 500ml	Anions 2:1 (30 days), pH + Conductivity (7 days)	
2287363	TP11 1.00 SOIL	04/12/23		PT 500ml	Organic Matter (Manual) (28 days)	
2287364	TP12 0.00 SOIL	29/11/23		PT 500ml	Anions 2:1 (30 days), pH + Conductivity (7 days)	

Key: P-Plastic T-Tub

DETS cannot be held responsible for the integrity of samples received whereby the laboratory did not undertake the sampling. In this instance samples received may be deviating. Deviating Sample criteria are based on British and International standards and laboratory trials in conjunction with the UKAS note 'Guidance on Deviating Samples'. All samples received are listed above. However, those samples that have additional comments in relation to hold time, inappropriate containers etc are deviating due to the reasons stated. This means that the analysis is accredited where applicable, but results may be compromised due to sample deviations. If no sampled date (soils) or date+time (waters) has been supplied then samples are deviating. However, if you are able to supply a sampled date (and time for waters) this will prevent samples being reported as deviating where specific hold times are not exceeded and where the container supplied is suitable.

## Information in Support of the Analytical Results

*Our Ref* 24-00916-0-1  
*Client Ref* ~ A15075-2  
*Contract* ~

### Soil Analysis Notes

Inorganic soil analysis was carried out on a dried sample, crushed to pass a 425µm sieve, in accordance with BS1377.  
Organic soil analysis was carried out on an 'as received' sample. Organics results are corrected for moisture and expressed on a dry weight basis.  
The Loss on Drying, used to express organics analysis on an air dried basis, is carried out at a temperature of 28°C +/-2°C.

### Disposal

From the issue date of this test certificate, samples will be held for the following times prior to disposal :-  
Soils - 1 month, Liquids - 2 weeks, Asbestos (test portion) - 6 months

#### Key:

~ Sample details are provided by the client and can affect the validity of the results  
\* -not accredited.  
# -MCERTS (accreditation only applies if report carries the MCERTS logo).  
\$ -subcontracted.  
n/s -not supplied.  
I/S -insufficient sample.  
U/S -unsuitable sample.  
t/f -to follow.  
nd -not detected.

**End of Report**



# DETS

## Certificate of Analysis

*Certificate Number* 24-00918-0

*Issued:*

*Client* Terra Tek  
62 Rochsolloch Road  
Airdrie  
ML6 9BG

*Our Reference* 24-00918-0

*Client Reference* A15075-3

*Order No* (not supplied)

*Contract Title* (not supplied)

*Description* 4 Soil samples.

*Date Received* 17-Jan-24

*Date Started* 17-Jan-24

*Date Completed* 04-Mar-24

*Test Procedures* Identified by prefix DETSn (details on request).

*Notes* **This report supersedes 24-00918, amendments made**

Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.

*Approved By*



Kirk Bridgewood  
General Manager



# Summary of Chemical Analysis

## Soil Samples

Our Ref 24-00918-0

Client Ref A15075-3

Contract Title

<b>Lab No</b>	2287371	2287372	2287373	2287374
<b>Sample ID</b>	BH14	BH28	BH28	TP36A
<b>Depth</b>	0.80	0.50	2.65	0.50
<b>Other ID</b>	201352	2013353	2013354	2013356
<b>Sample Type</b>	SOIL	SOIL	SOIL	SOIL
<b>Sampling Date</b>	14/12/2023	14/12/2023	14/12/2023	13/12/2023
<b>Sampling Time</b>	n/s	n/s	n/s	n/s

Test	Method	LOD	Units				
<b>Inorganics</b>							
pH	DETSC 2008#		pH	5.9			
Organic matter	DETSC 2002#	0.1	%		21	23	4.6
Sulphate Aqueous Extract as SO4 (2:1)	DETSC 2076#	10	mg/l	36			
Sulphur as S, Total	DETSC 2320	0.01	%	0.03			
Sulphate as SO4, Total	DETSC 2321#	0.01	%	0.05			



## Information in Support of the Analytical Results

Our Ref 24-00918-0  
 Client Ref A15075-3  
 Contract

### Containers Received & Deviating Samples

Lab No	Sample ID	Date		Containers Received	Holding time exceeded for tests	Inappropriate container for tests
		Sampled				
2287371	BH14 0.80 SOIL	14/12/23		PT 500ml	Anions 2:1 (30 days), Total Sulphur ICP (7 days), Total Sulphate ICP (30 days), pH + Conductivity (7 days)	
2287372	BH28 0.50 SOIL	14/12/23		PG	Organic Matter (Manual) (28 days)	
2287373	BH28 2.65 SOIL	14/12/23		PG	Organic Matter (Manual) (28 days)	
2287374	TP36A 0.50 SOIL	13/12/23		PT 500ml	Organic Matter (Manual) (28 days)	

Key: P-Plastic T-Tub G-Bag

DETS cannot be held responsible for the integrity of samples received whereby the laboratory did not undertake the sampling. In this instance samples received may be deviating. Deviating Sample criteria are based on British and International standards and laboratory trials in conjunction with the UKAS note 'Guidance on Deviating Samples'. All samples received are listed above. However, those samples that have additional comments in relation to hold time, inappropriate containers etc are deviating due to the reasons stated. This means that the analysis is accredited where applicable, but results may be compromised due to sample deviations. If no sampled date (soils) or date+time (waters) has been supplied then samples are deviating. However, if you are able to supply a sampled date (and time for waters) this will prevent samples being reported as deviating where specific hold times are not exceeded and where the container supplied is suitable.

### Soil Analysis Notes

Inorganic soil analysis was carried out on a dried sample, crushed to pass a 425µm sieve, in accordance with BS1377.

Organic soil analysis was carried out on an 'as received' sample. Organics results are corrected for moisture and expressed on a dry weight basis.

The Loss on Drying, used to express organics analysis on an air dried basis, is carried out at a temperature of 28°C +/-2°C.

### Disposal

From the issue date of this test certificate, samples will be held for the following times prior to disposal :-

Soils - 1 month, Liquids - 2 weeks, Asbestos (test portion) - 6 months

End of Report



# DETS

## Certificate of Analysis

*Certificate Number* 24-01789-0

*Issued:*

*Client* Terra Tek  
62 Rochsolloch Road  
Airdrie  
ML6 9BG

*Our Reference* 24-01789-0

*Client Reference* A15075-4

*Order No* (not supplied)

*Contract Title* A15075-4

*Description* 3 Soil samples.

*Date Received* 26-Jan-24

*Date Started* 29-Jan-24

*Date Completed* 04-Mar-24

*Test Procedures* Identified by prefix DETSn (details on request).

*Notes* **This report supersedes 24-01789, amendments made**

Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.

*Approved By*



Kirk Bridgewood  
General Manager



# Summary of Chemical Analysis

## Soil Samples

Our Ref 24-01789-0  
 Client Ref A15075-4  
 Contract Title A15075-4

<b>Lab No</b>	2292216	2292217	2292218
<b>Sample ID</b>	BH02	BH12	BH16
<b>Depth</b>	0.10	0.50	0.40
<b>Other ID</b>	2013667	2013669	2013670
<b>Sample Type</b>	SOIL	SOIL	SOIL
<b>Sampling Date</b>	09/01/2024	19/12/2023	18/12/2023
<b>Sampling Time</b>	n/s	n/s	n/s

Test	Method	LOD	Units			
<b>Inorganics</b>						
Loss on Ignition at 440oC	DETSC 2003#	0.01	%	57		
Organic matter	DETSC 2002#	0.1	%	> 25	2.4	2.1

## Information in Support of the Analytical Results

Our Ref 24-01789-0  
 Client Ref A15075-4  
 Contract A15075-4

### Containers Received & Deviating Samples

Lab No	Sample ID	Date		Containers Received	Holding time exceeded for tests	Inappropriate container for tests
		Sampled				
2292216	BH02 0.10 SOIL	09/01/24		PG		
2292217	BH12 0.50 SOIL	19/12/23		PG	Organic Matter (Manual) (28 days)	
2292218	BH16 0.40 SOIL	18/12/23		PG	Organic Matter (Manual) (28 days)	

Key: P-Plastic G-Bag

DETS cannot be held responsible for the integrity of samples received whereby the laboratory did not undertake the sampling. In this instance samples received may be deviating. Deviating Sample criteria are based on British and International standards and laboratory trials in conjunction with the UKAS note 'Guidance on Deviating Samples'. All samples received are listed above. However, those samples that have additional comments in relation to hold time, inappropriate containers etc are deviating due to the reasons stated. This means that the analysis is accredited where applicable, but results may be compromised due to sample deviations. If no sampled date (soils) or date+time (waters) has been supplied then samples are deviating. However, if you are able to supply a sampled date (and time for waters) this will prevent samples being reported as deviating where specific hold times are not exceeded and where the container supplied is suitable.

### Soil Analysis Notes

Inorganic soil analysis was carried out on a dried sample, crushed to pass a 425µm sieve, in accordance with BS1377.

Organic soil analysis was carried out on an 'as received' sample. Organics results are corrected for moisture and expressed on a dry weight basis.

The Loss on Drying, used to express organics analysis on an air dried basis, is carried out at a temperature of 28°C +/-2°C.

### Disposal

From the issue date of this test certificate, samples will be held for the following times prior to disposal :-

Soils - 1 month, Liquids - 2 weeks, Asbestos (test portion) - 6 months

End of Report